

PATENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

To:

Commissioner
 US Department of Commerce
 United States Patent and Trademark
 Office, PCT
 2011 South Clark Place Room
 CP2/5C24
 Arlington, VA 22202
 ETATS-UNIS D'AMERIQUE
 in its capacity as elected Office

Date of mailing (day/month/year) 02 March 2001 (02.03.01)	
International application No. PCT/GB00/02403	Applicant's or agent's file reference P009018WO KMB
International filing date (day/month/year) 21 June 2000 (21.06.00)	Priority date (day/month/year) 21 June 1999 (21.06.99)
Applicant BENNETT, Ricky et al	

1. The designated Office is hereby notified of its election made:

☒ in the demand filed with the International Preliminary Examining Authority on:
 11 January 2001 (11.01.01)

☐ in a notice effecting later election filed with the International Bureau on:

2. The election ☒ was
☐ was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland Facsimile No.: (41-22) 740.14.35	Authorized officer Zakaria EL KHODARY Telephone No.: (41-22) 338.83.38
---	--

THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

PCT

From the INTERNATIONAL BUREAU

NOTIFICATION OF THE RECORDING
OF A CHANGE(PCT Rule 92bis.1 and
Administrative Instructions, Section 422)

To:

BODEN, Keith, McMurray
Fry Heath & Spence
The Old College
53 High Street
Horley, Surrey RH6 7BN
ROYAUME-UNI

Date of mailing (day/month/year)

21 September 2001 (21.09.01)

Applicant's or agent's file reference

P58389B/KMB

IMPORTANT NOTIFICATION

International application No.

PCT/GB00/02403

International filing date (day/month/year)

21 June 2000 (21.06.00)

1. The following indications appeared on record concerning:

☐ the applicant ☐ the inventor ☒ the agent ☐ the common representative

Name and Address

BODEN, Keith, McMurray
D Young & Co.
21 New Fetter Lane
London EC4A 1DA
United Kingdom

State of Nationality

State of Residence

Telephone No.

+44 020 7353 4343

Facsimile No.

+44 020 7353 7777

Teleprinter No.

2. The International Bureau hereby notifies the applicant that the following change has been recorded concerning:

☐ the person ☐ the name ☒ the address ☐ the nationality ☐ the residence

Name and Address

BODEN, Keith, McMurray
Fry Heath & Spence
The Old College
53 High Street
Horley, Surrey RH6 7BN
United Kingdom

State of Nationality

State of Residence

Telephone No.

+44 (0) 1293 776880

Facsimile No.

+44 (0) 1293 776837

Teleprinter No.

3. Further observations, if necessary:

4. A copy of this notification has been sent to:

☒ the receiving Office ☐ the designated Offices concerned
☐ the International Searching Authority ☒ the elected Offices concerned
☒ the International Preliminary Examining Authority ☐ other:The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer

Dominique DELMAS

Telephone No.: (41-22) 338.83.38

THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

PCT

NOTIFICATION OF RECEIPT OF RECORD COPY

(PCT Rule 24.2(a))

From the INTERNATIONAL BUREAU

To:

BODEN, Keith, McMurray
D Young & Co.
21 New Fetter Lane
London EC4A 1DA
ROYAUME-UNI

SOUTHAMPTON

KMB 252 Patents noted

Date of mailing (day/month/year) 01 September 2000 (01.09.00)	IMPORTANT NOTIFICATION
Applicant's or agent's file reference P009018WO KMB	International application No. PCT/GB00/02403

The applicant is hereby notified that the International Bureau has received the record copy of the international application as detailed below.

Name(s) of the applicant(s) and State(s) for which they are applicants:

DEK PRINTING MACHINES LIMITED (for all designated States except US)
BENNETT, Ricky et al (for US)

International filing date : 21 June 2000 (21.06.00)
Priority date(s) claimed : 21 June 1999 (21.06.99)
13 March 2000 (13.03.00)
Date of receipt of the record copy by the International Bureau : 16 August 2000 (16.08.00)
List of designated Offices :

EP : AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE
National : CA, JP, US

ATTENTION

The applicant should carefully check the data appearing in this Notification. In case of any discrepancy between these data and the indications in the international application, the applicant should immediately inform the International Bureau.

In addition, the applicant's attention is drawn to the information contained in the Annex, relating to:

- ☒ time limits for entry into the national phase
- ☒ confirmation of precautionary designations
- ☒ requirements regarding priority documents

A copy of this Notification is being sent to the receiving Office and to the International Searching Authority.

The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland	Authorized officer: R. Chrem
Facsimile No. (41-22) 740.14.35	Telephone No. (41-22) 338.83.38

THIS PAGE BLANK (USPTO)

INFORMATION ON TIME LIMITS FOR ENTERING THE NATIONAL PHASE

The applicant is reminded that the "national phase" must be entered before each of the designated Offices indicated in the Notification of Receipt of Record Copy (Form PCT/IB/301) by paying national fees and furnishing translations, as prescribed by the applicable national laws.

The time limit for performing these procedural acts is **20 MONTHS** from the priority date or, for those designated States which the applicant elects in a demand for international preliminary examination or in a later election, **30 MONTHS** from the priority date, provided that the election is made before the expiration of 19 months from the priority date. Some designated (or elected) Offices have fixed time limits which expire even later than 20 or 30 months from the priority date. In other Offices an extension of time or grace period, in some cases upon payment of an additional fee, is available.

In addition to these procedural acts, the applicant may also have to comply with other special requirements applicable in certain Offices. It is the applicant's responsibility to ensure that the necessary steps to enter the national phase are taken in a timely fashion. Most designated Offices do not issue reminders to applicants in connection with the entry into the national phase.

For detailed information about the procedural acts to be performed to enter the national phase before each designated Office, the applicable time limits and possible extensions of time or grace periods, and any other requirements, see the relevant Chapters of Volume II of the PCT Applicant's Guide. Information about the requirements for filing a demand for international preliminary examination is set out in Chapter IX of Volume I of the PCT Applicant's Guide.

GR and ES became bound by PCT Chapter II on 7 September 1996 and 6 September 1997, respectively, and may, therefore, be elected in a demand or a later election filed on or after 7 September 1996 and 6 September 1997, respectively, regardless of the filing date of the international application. (See second paragraph above.)

Note that only an applicant who is a national or resident of a PCT Contracting State which is bound by Chapter II has the right to file a demand for international preliminary examination.

CONFIRMATION OF PRECAUTIONARY DESIGNATIONS

This notification lists only specific designations made under Rule 4.9(a) in the request. It is important to check that these designations are correct. Errors in designations can be corrected where precautionary designations have been made under Rule 4.9(b). The applicant is hereby reminded that any precautionary designations may be confirmed according to Rule 4.9(c) before the expiration of 15 months from the priority date. If it is not confirmed, it will automatically be regarded as withdrawn by the applicant. There will be no reminder and no invitation. Confirmation of a designation consists of the filing of a notice specifying the designated State concerned (with an indication of the kind of protection or treatment desired) and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.

REQUIREMENTS REGARDING PRIORITY DOCUMENTS

For applicants who have not yet complied with the requirements regarding priority documents, the following is recalled.

Where the priority of an earlier national, regional or international application is claimed, the applicant must submit a copy of the said earlier application, certified by the authority with which it was filed ("the priority document") to the receiving Office (which will transmit it to the International Bureau) or directly to the International Bureau, before the expiration of 16 months from the priority date, provided that any such priority document may still be submitted to the International Bureau before that date of international publication of the international application, in which case that document will be considered to have been received by the International Bureau on the last day of the 16-month time limit (Rule 17.1(a)).

Where the priority document is issued by the receiving Office, the applicant may, instead of submitting the priority document, request the receiving Office to prepare and transmit the priority document to the International Bureau. Such request must be made before the expiration of the 16-month time limit and may be subjected by the receiving Office to the payment of a fee (Rule 17.1(b)).

If the priority document concerned is not submitted to the International Bureau or if the request to the receiving Office to prepare and transmit the priority document has not been made (and the corresponding fee, if any, paid) within the applicable time limit indicated under the preceding paragraphs, any designated State may disregard the priority claim, provided that no designated Office may disregard the priority claim concerned before giving the applicant an opportunity to furnish the priority document within a time limit which is reasonable under the circumstances.

Where several priorities are claimed, the priority date to be considered for the purposes of computing the 16-month time limit is the filing date of the earliest application whose priority is claimed.

THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

PCT

NOTIFICATION CONCERNING
SUBMISSION OR TRANSMITTAL
OF PRIORITY DOCUMENT

(PCT Administrative Instructions, Section 411)

From the INTERNATIONAL BUREAU

To:

BODEN, Keith, McMurray
D Young & Co.
21 New Fetter Lane
London EC4A 1DA
ROYAUME-UNICOMPUTER
NOTED

DS KMB

Date of mailing (day/month/year) 13 October 2000 (13.10.00)	IMPORTANT NOTIFICATION
Applicant's or agent's file reference P009018WO KMB	
International application No. PCT/GB00/02403	International filing date (day/month/year) 21 June 2000 (21.06.00)
International publication date (day/month/year) Not yet published	Priority date (day/month/year) 21 June 1999 (21.06.99)
Applicant DEK PRINTING MACHINES LIMITED et al	

- The applicant is hereby notified of the date of receipt (except where the letters "NR" appear in the right-hand column) by the International Bureau of the priority document(s) relating to the earlier application(s) indicated below. Unless otherwise indicated by an asterisk appearing next to a date of receipt, or by the letters "NR", in the right-hand column, the priority document concerned was submitted or transmitted to the International Bureau in compliance with Rule 17.1(a) or (b).
- This updates and replaces any previously issued notification concerning submission or transmittal of priority documents.
- An asterisk(*) appearing next to a date of receipt, in the right-hand column, denotes a priority document submitted or transmitted to the International Bureau but not in compliance with Rule 17.1(a) or (b). In such a case, the attention of the applicant is directed to Rule 17.1(c) which provides that no designated Office may disregard the priority claim concerned before giving the applicant an opportunity, upon entry into the national phase, to furnish the priority document within a time limit which is reasonable under the circumstances.
- The letters "NR" appearing in the right-hand column denote a priority document which was not received by the International Bureau or which the applicant did not request the receiving Office to prepare and transmit to the International Bureau, as provided by Rule 17.1(a) or (b), respectively. In such a case, the attention of the applicant is directed to Rule 17.1(c) which provides that no designated Office may disregard the priority claim concerned before giving the applicant an opportunity, upon entry into the national phase, to furnish the priority document within a time limit which is reasonable under the circumstances.

<u>Priority date</u>	<u>Priority application No.</u>	<u>Country or regional Office or PCT receiving Office</u>	<u>Date of receipt of priority document</u>
21 June 1999 (21.06.99)	09/337,895	US	05 Sept 2000 (05.09.00)
13 Marc 2000 (13.03.00)	09/524,764	US	05 Sept 2000 (05.09.00)

The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland	Authorized officer Magda BOUACHA
Facsimile No. (41-22) 740.14.35	Telephone No. (41-22) 338.83.38

THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

PCT

NOTICE INFORMING THE APPLICANT OF THE
COMMUNICATION OF THE INTERNATIONAL
APPLICATION TO THE DESIGNATED OFFICES

(PCT Rule 47.1(c), first sentence)

From the INTERNATIONAL BUREAU

To:

BODEN, Keith, McMurray
D Young & Co.21 New Fetter Lane
London EC4A 3DA
ROYAUME-UNIP/901820
BODEN
1999
12/15/99
OSKUB

Date of mailing (day/month/year) 28 December 2000 (28.12.00)		
Applicant's or agent's file reference P009018WO KMB		IMPORTANT NOTICE
International application No. PCT/GB00/02403	International filing date (day/month/year) 21 June 2000 (21.06.00)	
Priority date (day/month/year) 21 June 1999 (21.06.99)		
Applicant DEK PRINTING MACHINES LIMITED et al		

1. Notice is hereby given that the International Bureau has communicated, as provided in Article 20, the international application to the following designated Offices on the date indicated above as the date of mailing of this Notice:
- US

In accordance with Rule 47.1(c), third sentence, those Offices will accept the present Notice as conclusive evidence that the communication of the international application has duly taken place on the date of mailing indicated above and no copy of the international application is required to be furnished by the applicant to the designated Office(s).

2. The following designated Offices have waived the requirement for such a communication at this time:
- CA, EP, JP

The communication will be made to those Offices only upon their request. Furthermore, those Offices do not require the applicant to furnish a copy of the international application (Rule 49.1(a-bis)).

3. Enclosed with this Notice is a copy of the international application as published by the International Bureau on 28 December 2000 (28.12.00) under No. WO 00/79858

REMINDER REGARDING CHAPTER II (Article 31(2)(a) and Rule 54.2)

If the applicant wishes to postpone entry into the national phase until 30 months (or later in some Offices) from the priority date, a demand for international preliminary examination must be filed with the competent International Preliminary Examining Authority before the expiration of 19 months from the priority date.

It is the applicant's sole responsibility to monitor the 19-month time limit.

Note that only an applicant who is a national or resident of a PCT Contracting State which is bound by Chapter II has the right to file a demand for international preliminary examination.

REMINDER REGARDING ENTRY INTO THE NATIONAL PHASE (Article 22 or 39(1))

If the applicant wishes to proceed with the international application in the national phase, he must, within 20 months or 30 months, or later in some Offices, perform the acts referred to therein before each designated or elected Office.


For further important information on the time limits and acts to be performed for entering the national phase, see the Annex to Form PCT/IB/301 (Notification of Receipt of Record Copy) and Volume II of the PCT Applicant's Guide.

The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland	Authorized officer J. Zahra
Facsimile No. (41-22) 740.14.35	Telephone No. (41-22) 338.83.38

THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

PCT



INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

Applicant's or agent's file reference P009018WO KMB	FOR FURTHER ACTION See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/GB00/02403	International filing date (day/month/year) 21/06/2000	Priority date (day/month/year) 21/06/1999
International Patent Classification (IPC) or national classification and IPC H05K13/00		
Applicant DEK PRINTING MACHINES LIMITED et al.		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.



2. This REPORT consists of a total of 7 sheets, including this cover sheet.

- ☐ This report is also accompanied by ANNEXES, i.e. sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

These annexes consist of a total of sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
- IV ☐ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☒ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☒ Certain observations on the international application

Date of submission of the demand 11/01/2001	Date of completion of this report 16.10.2001
Name and mailing address of the international preliminary examining authority:  European Patent Office D-80298 Munich Tel. +49 89 2399 - 0 Tx: 523656 epmu d Fax: +49 89 2399 - 4465	Authorized officer Molenaar, E Telephone No. +49 89 2399 2159 

THIS PAGE BLANK (USPTO)

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No. PCT/GB00/02403

I. Basis of the report

1. With regard to the **elements** of the international application (*Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17)*):

Description, pages:

1-34 as originally filed

Claims, No.:

1-80 as originally filed

Drawings, sheets:

1/18-18/18 as originally filed

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.

These elements were available or furnished to this Authority in the following language: , which is:

- ☐ the language of a translation furnished for the purposes of the international search (under Rule 23.1(b)).
- ☐ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of a translation furnished for the purposes of international preliminary examination (under Rule 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

- ☐ contained in the international application in written form.
- ☐ filed together with the international application in computer readable form.
- ☐ furnished subsequently to this Authority in written form.
- ☐ furnished subsequently to this Authority in computer readable form.
- ☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. The amendments have resulted in the cancellation of:

- ☐ the description, pages:
- ☐ the claims, Nos.:

THIS PAGE BLANK (USPTO)

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No. PCT/GB00/02403

☐ the drawings, sheets:

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed (Rule 70.2(c)):

(Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.)

6. Additional observations, if necessary:

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. Statement

Novelty (N)	Yes:	Claims	1 - 80
	No:	Claims	
Inventive step (IS)	Yes:	Claims	1 - 80
	No:	Claims	
Industrial applicability (IA)	Yes:	Claims	1 - 80
	No:	Claims	

2. Citations and explanations
see separate sheet

VI. Certain documents cited

1. Certain published documents (Rule 70.10)

and / or

2. Non-written disclosures (Rule 70.9)

see separate sheet

VIII. Certain observations on the international application

The following observations on the clarity of the claims, description, and drawings or on the question whether the claims are fully supported by the description, are made:
see separate sheet

THIS PAGE BLANK (USPTO)

Re Item V

Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

The application concerns a tooling fixture as defined in independent claims 1, 9, 26, 30, 32, 34, 51, 65, 66 and 80; a method for supporting a workpiece as defined in independent claims 46, 72 and 79 and a fixture block as defined in claim 70.

Reference is made to the document D1: GB-A-2 322 089.

The document D1 is regarded as being the closest prior art to the subject-matter of claim 1, and shows a tooling fixture comprising: a fixture block containing a plurality of parallel cylinders formed therein; a plurality of piston assemblies slideably fitted into said plurality of cylinders such that a portion of said piston assemblies can extend from the surface of said fixture block when said piston assemblies slide within said cylinders; at least one fluid reservoir connected in flow communication with said cylinders below said pistons.

The subject-matter of **claim 1** therefore differs from this known tooling fixture in that it comprises means for reversibly forcing fluid from said reservoir into said cylinders.

The subject-matter of claim 1 is therefore novel (Article 33(2) PCT).

The problem to be solved by the present invention may therefore be regarded as not only providing means for forcing the fluid into the cylinders, but also for drawing the fluid out of the cylinders again.

The solution to this problem proposed in claim 1 of the present application is considered as involving an inventive step (Article 33(3) PCT) because such reversible fluid forcing means is not shown in the available documents, nor made obvious thereby.

In D1 the fluid is preferably air, which is not pushed back again into the reservoir, but is ventilated into atmosphere.

THIS PAGE BLANK (USPTO)

The subject-matter of claim **9** differs from this known tooling fixture in that it comprises means for reversibly forcing fluid from said reservoir into said manifold and from there into said cylinders.

The subject-matter of claim **26** differs from this known tooling fixture in that it comprises a hydraulic pressure tube containing a main piston therein; and a pneumatic pressure source connected to said hydraulic **pressure** tube for applying a positive pneumatic pressure to said main piston.

The subject-matter of claims **30** and **32** differs from this known tooling fixture in that it comprises a fluid reservoir containing a floating main piston therein; and a pneumatic pressure source connected to said hydraulic tube for providing pressure to said main piston.

The subject-matter of claim **34** differs from this known tooling fixture in that it comprises a second fluid reservoir with a main piston slideably fitted therein, connected in flow communication with a first fluid reservoir cavity; and means for sliding said main piston within said second reservoir.

The subject-matter of claim **51** differs from this known tooling fixture in that it comprises a pressure sensor generating a signal that indicates a pressure of the fluid in the cylinders and a controller connected with the sensor and the valve for controlling the flow of fluid between the fluid source and the cylinders within the fixture block.

The subject-matter of claim **65** differs from this known tooling fixture in that it comprises pressure sensing means for sensing a pressure of fluid in the cylinders and control means connected with the sensing means for controlling fluid accumulator means and the valve means.

The subject-matter of claim **66** differs from this known tooling fixture in that it comprises a pressure sensor connected with the plurality of cylinders; and a controller connected with the valves, the sensor and the fluid accumulator.

The subject-matter of claim **80** differs from this known tooling fixture in that it comprises

THIS PAGE BLANK (USPTO)

fluid control means for displacing fluid in the reservoir to cause sliding of supporting elements slideably received in bores in the fixture body.

Document D1 also shows a method of supporting a workpiece from which the subject-matter of claim 46 differs in that the pneumatic pressure is now applied to a piston contained in a fluid reservoir connected to the cylinders to force fluid into said cylinders (to force the pistons to emerge for contacting said workpiece).

The subject-matter of claim 79 further differs from this known method in that the fixture block is moved toward the workpiece so that the extended piston ends contact a surface of the workpiece and when the fixture block reaches a predetermined distance from the workpiece, the movement is stopped and the valve between the cylinders and the hydraulic fluid source is closed.

The subject-matter of claim 72 further differs from the method known from D1 in that first a force is applied to the source of hydraulic fluid to move the fluid out of the cylinders to pull the pistons toward the bottoms of the cylinders so that the fixture block can be moved to a predetermined distance from the workpiece before the pistons are driven to the tops of the cylinders; and a pressure of the fluid within the cylinders is sensed and when it reaches a predetermined threshold, the valve between the cylinders and the hydraulic fluid source is closed.

Claim 70 defines a fixture block comprising three separate sections, a top section mounted to a top surface of a cylinder section which is mounted to the top section of a manifold section; pistons are slideably disposed in cylinder holes with ends thereof extending through holes in the top section; and the cylinder holes are aligned with a groove along the top surface of the manifold section.

Such a combination is neither shown nor suggested in the available documents.

The dependent claims define preferred embodiments of the invention according to the independent claim and as such also meet the requirements of the PCT with respect to novelty and inventive step.

THIS PAGE BLANK (USPTO)

**INTERNATIONAL PRELIMINARY
EXAMINATION REPORT - SEPARATE SHEET**

International application No. PCT/GB00/02403

Re Item VI

Certain documents cited

Certain published documents (Rule 70.10) -

Application No Patent No	Publication date (day/month/year)	Filing date (day/month/year)	Priority date (valid claim) (day/month/year)
EP-A-0 954 211	03.11.99	26.04.99	28.04.98
WO-A-00 08 905	17.02.00	30.07.99	01.08.98

These documents do not seem to disclose all features of the multiple independent claims of this international application.

Re Item VIII

Certain observations on the international application

Claims 30 and 32 lack clarity in that they define a second pneumatic pressure source connected to "said second valve", but a second valve is not defined earlier. Both claims define a valve assembly with a one way check valve and a pneumatic control valve, and after examining the description, page 6, it appears that in claim 30 and in claim 32 the pneumatic control valve is meant by "said second valve".
For the preliminary examination, both claims are interpreted in this way.

Claim 65 fails to define the essential feature that the pressure sensing means is connected to the control means. For this preliminary examination, it is assumed that this feature is present and that the ends of the pistons extend from the cylinders **above a surface of the tooling fixture**.

Claim 66 defines valves, each connected with the accumulator, without the accumulator being defined earlier. It is assumed that the source of fluid defined earlier is in the form of an accumulator, and that "accumulator" is meant instead of "actuator" in claim 66.

The method of claim 72 is interpreted in that the last step of closing the valve takes place when the pressure reaches a predetermined threshold.

THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

PCT

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference P009018WO KMB	FOR FURTHER ACTION see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.	
International application No. PCT/GB 00/ 02403	International filing date (day/month/year) 21/06/2000	(Earliest) Priority Date (day/month/year) 21/06/1999
Applicant DEK PRINTING MACHINES LIMITED		

This International Search Report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This International Search Report consists of a total of 4 sheets.



It is also accompanied by a copy of each prior art document cited in this report.

1. Basis of the report

- a. With regard to the **language**, the international search was carried out on the basis of the international application in the language in which it was filed, unless otherwise indicated under this item.



the international search was carried out on the basis of a translation of the international application furnished to this Authority (Rule 23.1(b)).

- b. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international search was carried out on the basis of the sequence listing :



contained in the international application in written form.



filed together with the international application in computer readable form.



furnished subsequently to this Authority in written form.



furnished subsequently to this Authority in computer readable form.



the statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.



the statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

2. ☐ **Certain claims were found unsearchable** (See Box I).

3. ☐ **Unity of Invention is lacking** (see Box II).

4. With regard to the title,

the text is approved as submitted by the applicant.



the text has been established by this Authority to read as follows:

5. With regard to the abstract,

the text is approved as submitted by the applicant.



the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.

6. The figure of the drawings to be published with the abstract is Figure No.

as suggested by the applicant.

1

None of the figures.



because the applicant failed to suggest a figure.



because this figure better characterizes the invention.

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

International application No.

PCT/GB 00/ 02403

Box III TEXT OF THE ABSTRACT (Continuation of Item 5 of the first sheet)

LIGNE 2:SUPPORTING ELEMENTS (12) FOR
LIGNE 4: ...ONE FLUID RESERVOIR (9)...
LIGNE 6: ...FLUID CONTROL MEANS (53)...

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

International Application No

PCT/GB 00/02403

A. CLASSIFICATION OF SUBJECT MATTER
IPC 7 H05K13/00

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)
IPC 7 H05K B41F

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

EPO-Internal, PAJ

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	GB 2 322 089 A (DEK PRINTING) 17 September 1997 (1997-09-17) the whole document	1,8,26, 30,32, 34,46, 51,65, 66,70,72
P,A	WO 00 08905 A (SMC PNEUMATICS) 17 February 2000 (2000-02-17) the whole document	1,8,26, 30,32, 34,46, 51,65, 66,70,72



Further documents are listed in the continuation of box C.



Patent family members are listed in annex.

* Special categories of cited documents :

- *A* document defining the general state of the art which is not considered to be of particular relevance
- *E* earlier document but published on or after the international filing date
- *L* document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- *O* document referring to an oral disclosure, use, exhibition or other means
- *P* document published prior to the international filing date but later than the priority date claimed

T later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

X document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

Y document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

& document member of the same patent family

Date of the actual completion of the international search

10 October 2000

Date of mailing of the international search report

18/10/2000

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040. Tx. 31 651 epo nl.
Fax: (+31-70) 340-3016

Authorized officer

Loncke, J

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

International Application No

PCT/GB 00/02403

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
P, A	EP 0 954 211 A (IMI NORGREN) 3 November 1999 (1999-11-03) the whole document -----	1, 8, 26, 30, 32, 34, 46, 51, 65, 66, 70, 72

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

Information on patent family members

International Application No

PCT/GB 00/02403

Patent document cited in search report		Publication date	Patent family member(s)		Publication date
GB 2322089	A	19-08-1998	EP	0960001 A	01-12-1999
			WO	9835780 A	20-08-1998

WO 0008905	A	17-02-2000	NONE		

EP 954211	A	03-11-1999	NONE		

THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

RECEIVED

From the
INTERNATIONAL PRELIMINARY EXAMINING AUTHORITY 18 OCT 2001

PCT

To:

BODEN, Dr Keith M.
FRY HEATH & SPENCE
The Old College
53 High Street
Horley, Surrey RH6 7BN
GRANDE BRETAGNE

NOTIFICATION OF TRANSMITTAL OF THE INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Rule 71.1)

Date of mailing
(day/month/year) 16.10.2001

Applicant's or agent's file reference
P009018WO KMB

IMPORTANT NOTIFICATION

International application No.
PCT/GB00/02403

International filing date (day/month/year)
21/06/2000

Priority date (day/month/year)
21/06/1999

Applicant
DEK PRINTING MACHINES LIMITED et al.

1. The applicant is hereby notified that this International Preliminary Examining Authority transmits herewith the international preliminary examination report and its annexes, if any, established on the international application.
2. A copy of the report and its annexes, if any, is being transmitted to the International Bureau for communication to all the elected Offices.
3. Where required by any of the elected Offices, the International Bureau will prepare an English translation of the report (but not of any annexes) and will transmit such translation to those Offices.

4. REMINDER

The applicant must enter the national phase before each elected Office by performing certain acts (filing translations and paying national fees) within 30 months from the priority date (or later in some Offices) (Article 39(1)) (see also the reminder sent by the International Bureau with Form PCT/IB/301).

Where a translation of the international application must be furnished to an elected Office, that translation must contain a translation of any annexes to the international preliminary examination report. It is the applicant's responsibility to prepare and furnish such translation directly to each elected Office concerned.

For further details on the applicable time limits and requirements of the elected Offices, see Volume II of the PCT Applicant's Guide.

Name and mailing address of the IPEA/

 European Patent Office
D-80298 Munich
Tel. +49 89 2399 - 0 Tx: 523656 epmu d
Fax: +49 89 2399 - 4465

Authorized officer

Mader, D

Tel. +49 89 2399-2744




THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

Applicant's or agent's file reference P009018WO KMB		FOR FURTHER ACTION	See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)
International application No. PCT/GB00/02403	International filing date (day/month/year) 21/06/2000	Priority date (day/month/year) 21/06/1999	
International Patent Classification (IPC) or national classification and IPC H05K13/00			
Applicant DEK PRINTING MACHINES LIMITED et al.			
<p>1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.</p> <p>2. This REPORT consists of a total of 7 sheets, including this cover sheet.</p> <p><input type="checkbox"/> This report is also accompanied by ANNEXES, i.e. sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).</p> <p>These annexes consist of a total of sheets.</p>			
<p>3. This report contains indications relating to the following items:</p> <ul style="list-style-type: none"> I <input checked="" type="checkbox"/> Basis of the report II <input type="checkbox"/> Priority III <input type="checkbox"/> Non-establishment of opinion with regard to novelty, inventive step and industrial applicability IV <input type="checkbox"/> Lack of unity of invention V <input checked="" type="checkbox"/> Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement VI <input checked="" type="checkbox"/> Certain documents cited VII <input type="checkbox"/> Certain defects in the international application VIII <input checked="" type="checkbox"/> Certain observations on the international application 			
Date of submission of the demand 11/01/2001		Date of completion of this report 16.10.2001	
Name and mailing address of the international preliminary examining authority:  European Patent Office D-80298 Munich Tel. +49 89 2399 - 0 Tx: 523656 epmu d Fax: +49 89 2399 - 4465		Authorized officer Molenaar, E Telephone No. +49 89 2399 2159	



THIS PAGE BLANK (USPTO)

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No. PCT/GB00/02403

I. Basis of the report

1. With regard to the **elements** of the international application (*Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17)*):

Description, pages:

1-34 as originally filed

Claims, No.:

1-80 as originally filed

Drawings, sheets:

1/18-18/18 as originally filed

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.

These elements were available or furnished to this Authority in the following language: , which is:

- ☐ the language of a translation furnished for the purposes of the international search (under Rule 23.1(b)).
- ☐ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of a translation furnished for the purposes of international preliminary examination (under Rule 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

- ☐ contained in the international application in written form.
- ☐ filed together with the international application in computer readable form.
- ☐ furnished subsequently to this Authority in written form.
- ☐ furnished subsequently to this Authority in computer readable form.
- ☐ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☐ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. The amendments have resulted in the cancellation of:

- ☐ the description, pages:
- ☐ the claims, Nos.:

THIS PAGE BLANK (USPTO)

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No. PCT/GB00/02403

☐ the drawings, sheets:

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed (Rule 70.2(c)):

(Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.)

6. Additional observations, if necessary:

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. Statement

Novelty (N)	Yes:	Claims	1 - 80
	No:	Claims	
Inventive step (IS)	Yes:	Claims	1 - 80
	No:	Claims	
Industrial applicability (IA)	Yes:	Claims	1 - 80
	No:	Claims	

2. Citations and explanations
see separate sheet

VI. Certain documents cited

1. Certain published documents (Rule 70.10)

and / or

2. Non-written disclosures (Rule 70.9)

see separate sheet

VIII. Certain observations on the international application

The following observations on the clarity of the claims, description, and drawings or on the question whether the claims are fully supported by the description, are made:
see separate sheet

THIS PAGE BLANK (USPTO)

**INTERNATIONAL PRELIMINARY
EXAMINATION REPORT - SEPARATE SHEET**

International application No. PCT/GB00/02403

Re Item V

Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

The application concerns a tooling fixture as defined in independent claims 1, 9, 26, 30, 32, 34, 51, 65, 66 and 80; a method for supporting a workpiece as defined in independent claims 46, 72 and 79 and a fixture block as defined in claim 70.

Reference is made to the document D1: GB-A-2 322 089.

The document D1 is regarded as being the closest prior art to the subject-matter of claim 1, and shows a tooling fixture comprising: a fixture block containing a plurality of parallel cylinders formed therein; a plurality of piston assemblies slideably fitted into said plurality of cylinders such that a portion of said piston assemblies can extend from the surface of said fixture block when said piston assemblies slide within said cylinders; at least one fluid reservoir connected in flow communication with said cylinders below said pistons.

The subject-matter of **claim 1** therefore differs from this known tooling fixture in that it comprises means for reversibly forcing fluid from said reservoir into said cylinders.

The subject-matter of claim 1 is therefore novel (Article 33(2) PCT).

The problem to be solved by the present invention may therefore be regarded as not only providing means for forcing the fluid into the cylinders, but also for drawing the fluid out of the cylinders again.

The solution to this problem proposed in claim 1 of the present application is considered as involving an inventive step (Article 33(3) PCT) because such reversible fluid forcing means is not shown in the available documents, nor made obvious thereby.

In D1 the fluid is preferably air, which is not pushed back again into the reservoir, but is ventilated into atmosphere.

THIS PAGE BLANK (USPTO)

**INTERNATIONAL PRELIMINARY
EXAMINATION REPORT - SEPARATE SHEET**

International application No. PCT/GB00/02403

The subject-matter of claim 9 differs from this known tooling fixture in that it comprises means for reversibly forcing fluid from said reservoir into said manifold and from there into said cylinders.

The subject-matter of claim 26 differs from this known tooling fixture in that it comprises a hydraulic pressure tube containing a main piston therein; and a pneumatic pressure source connected to said hydraulic pressure tube for applying a positive pneumatic pressure to said main piston.

The subject-matter of claims 30 and 32 differs from this known tooling fixture in that it comprises a fluid reservoir containing a floating main piston therein; and a pneumatic pressure source connected to said hydraulic tube for providing pressure to said main piston.

The subject-matter of claim 34 differs from this known tooling fixture in that it comprises a second fluid reservoir with a main piston slideably fitted therein, connected in flow communication with a first fluid reservoir cavity; and means for sliding said main piston within said second reservoir.

The subject-matter of claim 51 differs from this known tooling fixture in that it comprises a pressure sensor generating a signal that indicates a pressure of the fluid in the cylinders and a controller connected with the sensor and the valve for controlling the flow of fluid between the fluid source and the cylinders within the fixture block.

The subject-matter of claim 65 differs from this known tooling fixture in that it comprises pressure sensing means for sensing a pressure of fluid in the cylinders and control means connected with the sensing means for controlling fluid accumulator means and the valve means.

The subject-matter of claim 66 differs from this known tooling fixture in that it comprises a pressure sensor connected with the plurality of cylinders; and a controller connected with the valves, the sensor and the fluid accumulator.

The subject-matter of claim 80 differs from this known tooling fixture in that it comprises

THIS PAGE BLANK (USPTO)

**INTERNATIONAL PRELIMINARY
EXAMINATION REPORT - SEPARATE SHEET**

International application No. PCT/GB00/02403

fluid control means for displacing fluid in the reservoir to cause sliding of supporting elements slideably received in bores in the fixture body.

Document D1 also shows a method of supporting a workpiece from which the subject-matter of claim 46 differs in that the pneumatic pressure is now applied to a piston contained in a fluid reservoir connected to the cylinders to force fluid into said cylinders (to force the pistons to emerge for contacting said workpiece).

The subject-matter of claim 79 further differs from this known method in that the fixture block is moved toward the workpiece so that the extended piston ends contact a surface of the workpiece and when the fixture block reaches a predetermined distance from the workpiece, the movement is stopped and the valve between the cylinders and the hydraulic fluid source is closed.

The subject-matter of claim 72 further differs from the method known from D1 in that first a force is applied to the source of hydraulic fluid to move the fluid out of the cylinders to pull the pistons toward the bottoms of the cylinders so that the fixture block can be moved to a predetermined distance from the workpiece before the pistons are driven to the tops of the cylinders; and a pressure of the fluid within the cylinders is sensed and when it reaches a predetermined threshold, the valve between the cylinders and the hydraulic fluid source is closed.

Claim 70 defines a fixture block comprising three separate sections, a top section mounted to a top surface of a cylinder section which is mounted to the top section of a manifold section; pistons are slideably disposed in cylinder holes with ends thereof extending through holes in the top section; and the cylinder holes are aligned with a groove along the top surface of the manifold section.
Such a combination is neither shown nor suggested in the available documents.

The dependent claims define preferred embodiments of the invention according to the independent claim and as such also meet the requirements of the PCT with respect to novelty and inventive step.

THIS PAGE BLANK (USPTO)

**INTERNATIONAL PRELIMINARY
EXAMINATION REPORT - SEPARATE SHEET**

International application No. PCT/GB00/02403

Re Item VI

Certain documents cited

Certain published documents (Rule 70.10)

Application No Patent No	Publication date (day/month/year)	Filing date (day/month/year)	Priority date (valid claim) (day/month/year)
EP-A-0 954 211	03.11.99	26.04.99	28.04.98
WO-A-00 08 905	17.02.00	30.07.99	01.08.98

These documents do not seem to disclose all features of the multiple independent claims of this international application.

Re Item VIII

Certain observations on the international application

Claims 30 and 32 lack clarity in that they define a second pneumatic pressure source connected to "said second valve", but a second valve is not defined earlier. Both claims define a valve assembly with a one way check valve and a pneumatic control valve, and after examining the description, page 6, it appears that in claim 30 and in claim 32 the pneumatic control valve is meant by "said second valve".

For the preliminary examination, both claims are interpreted in this way.

Claim 65 fails to define the essential feature that the pressure sensing means is connected to the control means. For this preliminary examination, it is assumed that this feature is present and that the ends of the pistons extend from the cylinders **above a surface of the tooling fixture**.

Claim 66 defines valves, each connected with the accumulator, without the accumulator being defined earlier. It is assumed that the source of fluid defined earlier is in the form of an accumulator, and that "accumulator" is meant instead of "actuator" in claim 66.

The method of claim 72 is interpreted in that the last step of closing the valve takes place when the pressure reaches a predetermined threshold.



THIS PAGE BLANK (USPTO)

PATENT COOPERATION TREATY

From the RECEIVING OFFICE

PCT

NOTIFICATION OF THE INTERNATIONAL
APPLICATION NUMBER AND OF THE
INTERNATIONAL FILING DATE

(PCT Rule 20.5(c))

To:

D Young & Co
21 New Fetter Lane
London

EC4A 1DA

Date of mailing
(day/month/year)

07 JUL 2000

Applicant's or agents's file reference

P009018WO KMB

IMPORTANT NOTIFICATION

International application No.

PCT/GB00/02403

International filing date (day/month/year)

21/06/2000

Priority date (day/month/year)

21/06/1999

Applicant

DEK Printing Machines Limited et al

Title of the invention

Tooling Fixture

1. The applicant is hereby notified that the international application has been accorded the international application number and the international filing date indicated above.

2. The applicant is further notified that the record copy of the international application:

07 JUL 2000



was transmitted to the International Bureau on _____



has not yet been transmitted to the International Bureau for the reason indicated below and a copy of this notification has been sent to the International Bureau*:



because the necessary national security clearance has not yet been obtained.



because (reason to be specified):

* The International Bureau monitors the transmittal of the record copy by the receiving Office and will notify the applicant (with Form PCT/IB/301) of its receipt. Should the record copy not have been received by the expiration of 14 months from the priority date, the International Bureau will notify the applicant (Rule 22.1(c)).

Name and mailing address of the receiving Office

The Patent Office
Cardiff Road, Newport
South Wales NP9 1RH

Authorized officer

Phil Jones

Facsimile No.

Telephone No. 01633 814427

THIS PAGE BLANK (USPTO)



REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No.

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum)

P009018WO KMB

Box No. I TITLE OF INVENTION

TOOLING FIXTURE

Box No. II APPLICANT

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)

DEK PRINTING MACHINES LIMITED
Granby Industrial Estate
Weymouth
Dorset
DT4 9TH
United Kingdom

☐ This person is also inventor.

Telephone No.

Facsimile No.

Teleprinter No.

State (i.e. country) of nationality:

GB

State (i.e. country) of residence:

GB

This person is applicant for the purposes of:

☐ all designated States

☒ all designated States except the United States of America

☐ the United States of America only

☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)

BENNETT, Ricky
2 Plymouth Court
Flemington
NJ 08822
United States of America

This person is:

☐ applicant only

☒ applicant and inventor

☐ inventor only (if this check-box is marked, do not fill in below)

State (i.e. country) of nationality:

GB

State (i.e. country) of residence:

US

This person is applicant for the purposes of:

☐ all designated States

☐ all designated States except the United States of America

☒ the United States of America only

☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on a continuation sheet

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:

☒ agent

☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

BODEN, Dr Keith McMurray et al
D YOUNG & CO
21 New Fetter Lane
London
EC4A 1DA
United Kingdom

Telephone No.

+44 20 7353 4343

Facsimile No.

+44 20 7353 7777

Teleprinter No.

☐ Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

THIS PAGE BLANK (USPTO)

Continuation of Box No. III FURTHER APPLICANT (S) AND/OR (FURTHER) INVENTOR(S)

If none of the following sub-boxes is used, this sheet is not to be included in the request.

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

MONCAVAGE, Charles
4020 Freemansburg Avenue
Easton
PA 18045
United States of America

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (if this check-box is marked, do not fill in below)

State (that is, country) of nationality:

US

State (that is, country) of residence:

US

This person is applicant for the purposes of:

- ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

STARKE, Bernward
53 Queens Avenue
Dorchester
Dorset
DT1 2EP
United Kingdom

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (if this check-box is marked, do not fill in below)

State (that is, country) of nationality:

DE

State (that is, country) of residence:

GB

This person is applicant for the purposes of:

- ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

EDELSTEIN, Jason Mark
7 Windsor Court
Westerhall Road
Weymouth
Dorset
DT4 7SZ
United Kingdom

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (if this check-box is marked, do not fill in below)

State (that is, country) of nationality:

GB

State (that is, country) of residence:

GB

This person is applicant for the purposes of:

- ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

WOOD, Ian Gordon
380 Dorchester Road
Weymouth
Dorset
DT3 5AW
United Kingdom

This person is:

- ☐ applicant only
☒ applicant and inventor
☐ inventor only (if this check-box is marked, do not fill in below)

State (that is, country) of nationality:

GB

State (that is, country) of residence:

GB

This person is applicant for the purposes of:

- ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on a continuation sheet

THIS PAGE BLANK (USPTO)

Box No. V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☐ **AP** ARIPO Patent: GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☐ **EA** Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ **EP** European Patent: AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☐ **OA** OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, please specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|---|---|
| <input type="checkbox"/> AE United Arab Emirates | <input type="checkbox"/> LS Lesotho |
| <input type="checkbox"/> AL Albania | <input type="checkbox"/> LT Lithuania |
| <input type="checkbox"/> AM Armenia | <input type="checkbox"/> LU Luxembourg |
| <input type="checkbox"/> AT Austria | <input type="checkbox"/> LV Latvia |
| <input type="checkbox"/> AU Australia | <input type="checkbox"/> MA Morocco |
| <input type="checkbox"/> AZ Azerbaijan | <input type="checkbox"/> MD Republic of Moldova |
| <input type="checkbox"/> BA Bosnia and Herzegovina | <input type="checkbox"/> MG Madagascar |
| <input type="checkbox"/> BB Barbados | <input type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input type="checkbox"/> BG Bulgaria | |
| <input type="checkbox"/> BR Brazil | <input type="checkbox"/> MN Mongolia |
| <input type="checkbox"/> BY Belarus | <input type="checkbox"/> MW Malawi |
| <input checked="" type="checkbox"/> CA Canada | <input type="checkbox"/> MX Mexico |
| <input type="checkbox"/> CH AND LI Switzerland and Liechtenstein | <input type="checkbox"/> NO Norway |
| <input type="checkbox"/> CN China | <input type="checkbox"/> NZ New Zealand |
| <input type="checkbox"/> CR Costa Rica | <input type="checkbox"/> PL Poland |
| <input type="checkbox"/> CU Cuba | <input type="checkbox"/> PT Portugal |
| <input type="checkbox"/> CZ Czech Republic | <input type="checkbox"/> RO Romania |
| <input type="checkbox"/> DE Germany | <input type="checkbox"/> RU Russian Federation |
| <input type="checkbox"/> DK Denmark | <input type="checkbox"/> SD Sudan |
| <input type="checkbox"/> DM Dominica | <input type="checkbox"/> SE Sweden |
| <input type="checkbox"/> EE Estonia | <input type="checkbox"/> SG Singapore |
| <input type="checkbox"/> ES Spain | <input type="checkbox"/> SI Slovenia |
| <input type="checkbox"/> FI Finland | <input type="checkbox"/> SK Slovakia |
| <input type="checkbox"/> GB United Kingdom | <input type="checkbox"/> SL Sierra Leone |
| <input type="checkbox"/> GD Grenada | <input type="checkbox"/> TJ Tajikistan |
| <input type="checkbox"/> GE Georgia | <input type="checkbox"/> TM Turkmenistan |
| <input type="checkbox"/> GH Ghana | <input type="checkbox"/> TR Turkey |
| <input type="checkbox"/> GM Gambia | <input type="checkbox"/> TT Trinidad and Tobago |
| <input type="checkbox"/> HR Croatia | <input type="checkbox"/> TZ United Republic of Tanzania |
| <input type="checkbox"/> HU Hungary | <input type="checkbox"/> UA Ukraine |
| <input type="checkbox"/> ID Indonesia | <input type="checkbox"/> UG Uganda |
| <input type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> US United States of America |
| <input type="checkbox"/> IN India | |
| <input type="checkbox"/> IS Iceland | <input type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> JP Japan | <input type="checkbox"/> VN Viet Nam |
| <input type="checkbox"/> KE Kenya | <input type="checkbox"/> YU Yugoslavia |
| <input type="checkbox"/> KG Kyrgyzstan | <input type="checkbox"/> ZA South Africa |
| <input type="checkbox"/> KP Democratic People's Republic of Korea | <input type="checkbox"/> ZW Zimbabwe |
| <input type="checkbox"/> KR Republic of Korea | |
| <input type="checkbox"/> KZ Kazakhstan | |
| <input type="checkbox"/> LC Saint Lucia | |
| <input type="checkbox"/> LK Sri Lanka | |
| <input type="checkbox"/> LR Liberia | |

Check-boxes reserved for designating States (for the purposes of a national patent) which have become party to the PCT after the issuance of this sheet:

- ☐ DZ Algeria
- ☐ AG Antigua and Barbuda
- ☐ MZ Mozambique
- ☐ BZ Belize

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation (including fees) must reach the receiving Office within the 15-month time limit.)

THIS PAGE BLANK (USPTO)

Box No. VI PRIORITY CLAIM

Further priority claims are indicated in the Supplemental Box

Filing Date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application: * regional Office	international application: receiving Office
item (1) 21 Jun 1999 21/6/1999	09/337,895	US		
item (2) 13 Mar 2000 13/3/2000	09/524,764	US		
item (3)				

☐ The receiving Office is hereby requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s):

* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA)
(If two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

ISA / EP

Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):

Date (day/month/year)

Number:

Country (or regional Office):

Box No. VII CHECK LIST; LANGUAGE OF FILING

This international application contains the following number of sheets:

request : 4
description (excluding
sequence listing part) : 30
claims : 14
abstract : 1
drawings : 18
sequence listing part of
description :
Total number of
sheets : 67

This international application is accompanied by the item(s) marked below:

1. ☐ fee calculation sheet
2. ☐ separate signed power of attorney
3. ☐ copy of general power of attorney; reference number, if any:
4. ☐ statement explaining lack of signature
5. ☐ priority documents(s) identified in Box No. VI as item(s):
6. ☐ translation of international application into (language):
7. ☐ separate indications concerning deposited microorganism or other biological material
8. ☐ nucleotide and/or amino acid sequence listing in computer readable form
9. ☐ other (specify):

Figure of the drawings which
should accompany the abstract: 1

Language of filing of the
international application:

English

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request)

BODEN, Dr Keith McMurray

For receiving Office use only

1. Date of actual receipt of the purported international application:	2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:	
4. Date of timely receipt of the required corrections under PCT Article 11(2):	
5. International Searching Authority specified (if two or more are competent): ISA /	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee paid

For International Bureau use only

Date of receipt of the record copy by
the International Bureau:

THIS PAGE BLANK (USPTO)

(12) INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
28 December 2000 (28.12.2000)

PCT

(10) International Publication Number
WO 00/79858 A1

(51) International Patent Classification⁷: **H05K 13/00**

(21) International Application Number: **PCT/GB00/02403**

(22) International Filing Date: **21 June 2000 (21.06.2000)**

(25) Filing Language: **English**

(26) Publication Language: **English**

(30) Priority Data:
09/337,895 21 June 1999 (21.06.1999) US
09/524,764 13 March 2000 (13.03.2000) US

[DE/GB]: 53 Queens Avenue, Dorchester, Dorset DT1 2EP (GB). **EDELSTEIN, Jason, Mark** [GB/GB]: 7 Windsor Court, Westerhall Road, Weymouth, Dorset DT4 7SZ (GB). **WOOD, Ian, Gordon** [GB/GB]: 380 Dorchester Road, Weymouth, Dorset DT3 5AW (GB).

(74) Agent: **BODEN, Keith, McMurray**; D Young & Co., 21 New Fetter Lane, London EC4A 1DA (GB).

(81) Designated States (national): CA, JP, US.

Designated States (regional): European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE).

(71) Applicant (for all designated States except US): **DEK PRINTING MACHINES LIMITED** [GB/GB]; Granby Industrial Estate, Weymouth, Dorset DT4 9TH (GB).

Published:


- With international search report.
- Before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments.

(72) Inventors; and

(75) Inventors/Applicants (for US only): **BENNETT, Ricky** [GB/US]; 2 Plymouth Court, Flemington, NJ 08822 (US). **MONCAVAGE, Charles** [US/US]; 4020 Freemansburg Avenue, Easton, PA 18045 (US). **STARKE, Bernward**

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: **TOOLING FIXTURE**



(57) Abstract: A tooling fixture for supporting a workpiece, comprising: a body including a surface over which a workpiece is in use supported and a plurality of bores therein; a plurality of supporting elements (12) for supporting the workpiece, each slideably disposed in a respective one of the bores such as to be extendable from the surface of the body; at least one fluid reservoir (9) operably in fluid communication with the supporting elements such as to cause sliding of ones of the supporting elements on displacement of the fluid in the at least one fluid reservoir; and fluid control means (53) for displacing the fluid in the at least one reservoir such as to cause the supporting elements to be extended to a supporting position in contact with the workpiece and locking the supporting elements in the supporting position.

WO 00/79858 A1

THIS PAGE BLANK (USPTO)

PCT/GB 00/02403

IPC 7 H05K13/00

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 H05K B41F

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

EPO-Internal, PAJ

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	GB 2 322 089 A (DEK PRINTING) 17 September 1997 (1997-09-17)	1, 8, 26, 30, 32, 34, 46, 51, 65, 66, 70, 72
P, A	WO 00 08905 A (SMC PNEUMATICS) 17 February 2000 (2000-02-17)	1, 8, 26, 30, 32, 34, 46, 51, 65, 66, 70, 72

X Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents :

"A" document defining the general state of the art which is not considered to be of particular relevance

"E" earlier document but published on or after the international filing date

"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

"O" document referring to an oral disclosure, use, exhibition or other means

P document published prior to the international filing date but later than the priority date claimed

T later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

& document member of the same patent family

Date of the actual completion of the international search

10 October 2000

Date of mailing of the international search report

18/10/2000

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl.
Fax: (+31-70) 340-3016

Authorized officer

Loncke, J

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

International Application No

PCT/GB 00/02403

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
P,A	EP 0 954 211 A (IMI NORGRN) 3 November 1999 (1999-11-03) the whole document -----	1,8,26, 30,32, 34,46, 51,65, 66,70,72

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

Information on patent family members

International Application No

PCT/GB 00/02403

Patent document cited in search report		Publication date	Patent family member(s)	Publication date
GB 2322089	A	19-08-1998	EP 0960001 A	01-12-1999
			WO 9835780 A	20-08-1998
WO 0008905	A	17-02-2000	NONE	
EP 954211	A	03-11-1999	NONE	

THIS PAGE BLANK (USPTO)

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
28 December 2000 (28.12.2000)

PCT

(10) International Publication Number
WO 00/79858 A1

(51) International Patent Classification⁷: **H05K 13/00**

(21) International Application Number: **PCT/GB00/02403**

(22) International Filing Date: **21 June 2000 (21.06.2000)**

(25) Filing Language: **English**

(26) Publication Language: **English**

(30) Priority Data:
09/337,895 21 June 1999 (21.06.1999) US
09/524,764 13 March 2000 (13.03.2000) US

(71) Applicant (for all designated States except US): **DEK PRINTING MACHINES LIMITED** [GB/GB]; Granby Industrial Estate, Weymouth, Dorset DT4 9TH (GB).

(72) Inventors; and

(75) Inventors/Applicants (for US only): **BENNETT, Ricky** [GB/US]; 2 Plymouth Court, Flemington, NJ 08822 (US). **MONCAVAGE, Charles** [US/US]; 4020 Freemansburg Avenue, Easton, PA 18045 (US). **STARKE, Bernward**

[DE/GB]: 53 Queens Avenue, Dorchester, Dorset DT1 2EP (GB). **EDELSTEIN, Jason, Mark** [GB/GB]; 7 Windsor Court, Westerhall Road, Weymouth, Dorset DT4 7SZ (GB). **WOOD, Ian, Gordon** [GB/GB]; 380 Dorchester Road, Weymouth, Dorset DT3 5AW (GB).

(74) Agent: **BODEN, Keith, McMurray**; D Young & Co., 21 New Fetter Lane, London EC4A 1DA (GB).

(81) Designated States (national): CA, JP, US.


(84) Designated States (regional): European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE).

Published:

- With international search report.
- Before the expiration of the time limit for amending the claims and to be republished in the event of receipt of amendments.

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

(54) Title: **TOOLING FIXTURE**



(57) Abstract: A tooling fixture for supporting a workpiece, comprising: a body including a surface over which a workpiece is in use supported and a plurality of bores therein; a plurality of supporting elements (12) for supporting the workpiece, each slideably disposed in a respective one of the bores such as to be extendable from the surface of the body; at least one fluid reservoir (9) operably in fluid communication with the supporting elements such as to cause sliding of ones of the supporting elements on displacement of the fluid in the at least one fluid reservoir; and fluid control means (53) for displacing the fluid in the at least one reservoir such as to cause the supporting elements to be extended to a supporting position in contact with the workpiece and locking the supporting elements in the supporting position.

WO 00/79858 A1

THIS PAGE BLANK (USPTO)

TOOLING FIXTURE

The present invention relates to a tooling fixture for and a method of supporting a workpiece. In particular, the present invention relates to a hydraulic tooling fixture for supporting a flexible substrate such as a printed circuit board in a screen printing machine or a placement machine.

The fabrication of large volumes of electronic circuits is in practice accomplished using automated equipment. Typically, a viscous solder paste is first applied to a printed circuit board using a stencil printing machine, with the solder paste being applied to selected areas of a printed circuit board through a stencil, and electronic components are then placed on the applied solder paste using a placement machine, often referred to as a pick-and-place machine. The printed circuit board and components are then heated in a re-flow oven to a temperature sufficient to melt the solder paste, causing the molten solder to flow over the leads of the components and adjacent areas of the printed circuit board, and thereby form solder joints to complete the electronic circuit.

Such screen printing machines and placement machines normally include a tooling fixture for supporting the lower surface of the printed circuit board during processing. In screen printing machines, the printed circuit board is raised by the tooling fixture until the upper surface of the printed circuit board contacts the stencil. In this raised position, solder paste is applied under pressure to the upper surface of the stencil. The pressure applied by the printing head forces solder paste through the apertures in the stencil and onto the upper surface of the printed circuit board, with the tooling fixture preventing flexure of the printed circuit board away from the stencil during printing. In placement machines, a pick-and-place head sequentially presses electronic components onto predetermined locations on the printed circuit board, with the tooling fixture preventing the printed circuit board from flexing as pressure is applied thereto by the pick-and-place head.

Where components are provided on only one surface of the board, the tooling fixtures merely have to support a flat surface, and only slight modifications need to be made to the

fixtures to accommodate boards of different dimension. However, in order to better utilize the surface area of printed circuit boards and produce more compact circuitry, components are often placed on both surfaces of those boards. In such cases, after components have been mounted to one surface of the board, the board is then inverted and components are mounted to the other surface of the board. Consequently, a second tooling fixture is required which conforms to the three-dimensional surface created by the components mounted on the one surface of the board. Since each different circuit layout has a different three-dimensional shape, this second tooling fixture has to be customized for each layout.

A customized tooling fixture can be formed by manually arranging blocks on the upper surface of the tooling fixture such as to contact the portions of the board not populated by components. However, this technique is time consuming because an operator must re-position the blocks each time a printed circuit board having a different circuit layout is to be processed. This technique is particularly cumbersome when a large number of different types of circuit boards are fabricated on the same assembly line.

A customized tooling fixture can also be provided by an array of electronically-addressable posts which are retracted at positions where a component is mounted to the printed circuit board, and extended to contact the board surface to provide support. A computer program directs the tooling fixture to configure the posts to conform to each printed circuit board to be fabricated. This method provides a faster means to change from one tooling configuration to another as compared to the manual assembly of blocks. However, a separate computer database must be created for the layout of each board. Further, since no support is provided to the board in areas populated by components, certain areas of the board may be inadequately supported. Unsupported areas of the board can flex during processing resulting in misalignment between the stencil or the pick-and-place head and the board.

A customized tooling fixture can further be provided by a robot mechanism which draws support pillars from a reservoir and locates those pillars in the required positions to support the board. This method is faster and more consistent than manually arranging support

blocks, but again a separate computer database for each board type in order to define where pillars should be located, and can only provide support where there is clear space on the board to contact the pillars.

Prior to using a customized fixture with a new board layout, an operator must carefully inspect the fit between the tooling fixture and the board to make certain that misalignment and dimensional tolerances do not cause a block, extended post or positioned pillar to contact a component. Such contact will cause the tooling fixture to flex the board upward resulting in misplacement of the solder paste or components. More importantly, flexure of the board upwardly against the stencil can cause damage to the stencil or printing head of the screen printing machine.

Inspection of the tooling fixture each time a new type of board is to be fabricated complicates the manufacturing process and lowers throughput. Further, if the operator fails to properly inspect the fit between the board and the tooling fixture, large numbers of misaligned boards may be produced or costly damage to the equipment may result.

Furthermore, even when a fabrication line produces only a single type of printed circuit board, each surface of the board requires a different tooling fixture surface. A "flat" tooling fixture supports the unpopulated surface of the board while the other surface is screen printed and populated with components, and then a customized tooling fixture supports the now populated surface while the other surface of the board is screen printed and populated with components. Even this tooling change reduces the throughput of the fabrication line.

In view of the above-identified problems associated with known tooling fixtures, it is an aim of the present invention to provide a tooling fixture which conforms to the shape of an irregular surface of a workpiece, such as a printed circuit board having components fixed to the lower surface thereof, to be supported without requiring prior configuration or information as to the shape of the surface to be supported.

Accordingly, the present invention provides a tooling fixture for supporting a workpiece, comprising: a body including a surface over which a workpiece is in use supported and a plurality of bores therein; a plurality of supporting elements for supporting the workpiece, each slideably disposed in a respective one of the bores such as to be extendable from the surface of the body; at least one fluid reservoir operably in fluid communication with the supporting elements such as to cause sliding of ones of the supporting elements on displacement of the fluid in the at least one fluid reservoir; and fluid control means for displacing the fluid in the at least one reservoir such as to cause the supporting elements to be extended to a supporting position in contact with the workpiece and locking the supporting elements in the supporting position.

Of one aspect of the present invention a block is provided with a plurality of cylinders. Each cylinder surrounds a piston that drives a rod extending out of the top surface of the block. The cylinders are connected with a pressure sensor and an accumulator. A controllable valve is connected between the accumulator and the cylinders. Opening the valve allows hydraulic fluid to flow between the cylinders and the accumulator. The pressure sensor monitors the hydrostatic pressure of the hydraulic fluid in the cylinders. A compressed air source is connected to the accumulator through a further valve, such that when this valve is opened a force is generated to drive fluid into the cylinders, thereby causing the pistons to extend from the block. Similarly a vacuum source is also connected to the accumulator through a third valve, such that with this valve open and the compressed air valve closed, a vacuum is applied to the accumulator to draw fluid from the cylinders, thereby causing the pistons to retract into the block. The pressure sensor and the valve are connected with a controller that opens and closes the valve in response to a control sequence and the hydrostatic pressure in the cylinders.

The tooling fixture of this aspect conforms to an uneven surface as follows. The controller opens the fluid valve and the vacuum valve to draw fluid from the cylinders causing the pistons to retract the rods into the block. A workpiece is positioned above the fixture. The workpiece can be substantially flat or can have three-dimensional structures fixed thereon. Of one embodiment, the workpiece is a printed circuit that is either populated with

components or else unpopulated. The controller closes the vacuum valve and opens the compressed air valve, forcing fluid into the cylinders and raising the rods. When all of the rods have contacted the surface of the workpiece, the pressure of the fluid sensed by the pressure sensor rises. When this pressure reaches a predetermined threshold, the controller closes the fluid valve and the compressed air valve, and the positions of the rods are fixed. Force applied to the top surface of the workpiece, for example by the printhead of a screen printing machine, is opposed by the rods and deflection of the workpiece is prevented.

Of another embodiment of the present invention a tooling fixture module is provided with a plurality of cylinders. Each cylinder surrounds a piston wherein a portion of the piston extends out of the top surface of the module. The cylinders are connected with a fluid reservoir and pressure source. A control valve assembly is connected between the fluid reservoir and the cylinders. Opening the valve permits fluid to flow between the cylinders and the fluid reservoir, providing for raising or lowering the pistons.

The tooling fixture of this aspect conforms to an uneven surface as follows. Pneumatic pressure acts on a main piston, located within a fluid source. The fluid then acts on a control valve while in its open position in order to provide fluid to the cylinders of the module, causing a portion of the pistons to extend out of the module body. A workpiece is positioned above the tooling fixture. The workpiece can be substantially flat or can have three-dimensional structures fixed thereon. This workpiece can be a printed circuit that is either populated with components or else unpopulated. Each piston that makes contact with the workpiece will remain in this contact position while the other pistons continue to extend out of the module. After all of the pistons have made contact with the workpiece, the control valve closes, preventing the fluid from further entering or leaving the cylinders, thus effectively locking the pistons in a fixed position. Force applied to the top surface of the workpiece, for example, by the printhead of a screen printing machine is opposed by each piston, and deflection of the workpiece is prevented. In order to lower the pistons, the control valve opens, allowing the fluid to exit the cylinders through the valve, and the pistons will retract back into the module.

Of another embodiment of the invention, the fluid source can be in the form of a hydraulic tube containing a first main piston therein for forcing fluid towards the control valve and into the cylinders causing the pistons to move upward extending a portion thereof out of the surface of the module.

Of another embodiment of the invention, the hydraulic tube can be replaced with a fluid reservoir.

Of a further embodiment of the invention, a second fluid reservoir is used in conjunction with the first fluid reservoir to force fluid into cylinder sections above the pistons. A second pneumatic pressure source applies pressure directly to the control valve and to the second fluid reservoir simultaneously. Consequently the control valve is opened and allows fluid to flow from the cylinder sections below the pistons into the first fluid reservoir while fluid from the second reservoir is forced into the cylinder sections above the pistons, causing a portion of the pistons to retract into the module. Similarly, a first pneumatic pressure can be applied to the first fluid reservoir in order to force fluid through the control valve and into cylinder sections below the pistons. This will force the fluid contained in the cylinder sections above the pistons back into the second fluid reservoir, thus raising a portion of the pistons out of the module.

Of a further embodiment of the invention the cylinder and piston assemblies are replaced with rod assemblies each containing support rods, integrally connected at their bottom portions by a large singular cavity. Applying a first pneumatic pressure to a main piston within a fluid reservoir will force fluid through a one-way path in a control valve and into the large singular cavity. The fluid in the large singular cavity will force the support rods to extend out of the module until each of the rod makes contact with the workpiece. To retract the support rods, a second pneumatic pressure is applied to the control valve assembly to open a flow path allowing the fluid to flow from the large singular cavity to the fluid reservoir.

Of another embodiment of the invention the control valve is replaced with a permanent aperture between a single reservoir and a large singular cavity below a series of rod assemblies. The single reservoir includes a main piston with a main rod connected thereto it. A first pneumatic pressure source acts on the main rod and main piston to extend the combination towards the fluid within the fluid reservoir, forcing the fluid within the fluid reservoir through the permanent aperture and into the large singular cavity, thus raising the rods. A second pneumatic pressure source acts on the main rod and main piston to retract the combination away from the fluid within the fluid reservoir, drawing the fluid out of the large singular cavity and back into the fluid reservoir, thus retracting the rods. A third pneumatic pressure source acts on a clamp provided to prevent or allow the main piston and main rod combination within the reservoir to move. In effect, when pressure is applied to the clamp, the main rod is disengaged and permitted to move upon application of pressure applied to it from either the first or second pneumatic pressure source.

Preferred embodiments of the present invention will now be described hereinbelow by way of example only with reference to the accompanying drawings, in which:

Figure 1 schematically illustrates a cross-sectional view of a tooling fixture in accordance with a first embodiment of the present invention:

Figure 2 schematically illustrates a cross-sectional view of the tooling fixture of Figure 1 in a first, workpiece-receiving position;

Figure 3 schematically illustrates a cross-sectional view of the tooling fixture of Figure 1 in a second, workpiece-engaging position with the supporting rods partly extended;

Figure 4 schematically illustrates a cross-sectional view of the tooling fixture of Figure 1 in a third, workpiece-supporting position;

Figure 5 schematically illustrates a plan view of a tooling fixture in accordance with a second embodiment of the present invention;

Figure 6 schematically illustrates a plan view of a tooling fixture in accordance with a third embodiment of the present invention;

Figure 7 schematically illustrates a plan view of a tooling fixture in accordance with a fourth embodiment of the present invention;

Figure 8 illustrates an exploded perspective view of a tooling fixture module of a tooling fixture in accordance with a fifth embodiment of the present invention;

Figure 9 schematically illustrates a cross-sectional view of a tooling fixture in accordance with a sixth embodiment of the present invention;

Figure 10 illustrates a perspective view of one tooling fixture module of the tooling fixture of Figure 9;

Figure 11 illustrates a perspective view of one piston assembly of the tooling fixture of Figure 9;

Figure 12 illustrates a perspective view of the piston unit of the piston assembly of Figure 11;

Figure 13 schematically illustrates a cross-sectional view of a tooling fixture in accordance with a seventh embodiment of the present invention;

Figure 14 schematically illustrates a cross-sectional view of a tooling fixture in accordance with an eighth embodiment of the present invention;

Figure 15 schematically illustrates a cross-sectional view of a tooling fixture in accordance with a ninth embodiment of the present invention;

Figure 16 illustrates a perspective view of a tooling fixture module of a tooling fixture in accordance with a tenth embodiment of the present invention;

Figure 17 illustrates a plan view of the tooling fixture module of Figure 16;

Figure 18 illustrates a cross-sectional view (along section A-A) of the tooling fixture module of Figure 16;

Figure 19 illustrates in enlarged scale one part (part B) of the cross-sectional view of Figure 18;

Figure 20 illustrates in enlarged scale another part (part C) of the cross-sectional view of Figure 18, illustrated in a first, open configuration:

Figure 21 illustrates in enlarged scale the other part (part C) of the cross-sectional view of Figure 18, illustrated in a second, closed configuration;

Figure 22 illustrates a cross-sectional view of a tooling fixture module of a tooling fixture in accordance with an eleventh embodiment of the present invention;

Figure 23 illustrates in enlarged scale one part (part D) of the cross-sectional view of Figure 22;

Figure 24 illustrates in enlarged scale another part (part E) of the cross-sectional view of Figure 22; and

Figure 25 illustrates in enlarged scale a vertical sectional view (along section F-F) of the tooling fixture module of Figure 22.

Figures 1 to 4 illustrate a tooling fixture in accordance with a first embodiment of the present invention.

The tooling fixture comprises a fixture block 3 having upper and lower, in this embodiment substantially parallel, surfaces 4, 5, the upper surface 4 defining a surface over which a workpiece is to be supported and the lower surface 5 being supported on a platform which can be of fixed position or moved vertically so as to raise or lower the fixture block 3. The fixture block 3 includes a plurality of cylinders 7, which in this embodiment extend substantially orthogonally to the upper surface 4 thereof and are arranged as a plurality of parallel rows, and a cavity 9, which acts as a manifold, connecting ones, in this embodiment the lower, ends of the cylinders 7. The fixture block 3 further includes a plurality of apertures 10 in the upper surface 4 thereof corresponding to the respective cylinders 7, and a port 11 in fluid communication with the cavity 9.

The tooling fixture further comprises a plurality of piston units 12 slideably disposed in respective ones of the cylinders 7 such as to be driven on applying a hydraulic pressure into the cavity 9. Each piston assembly 12 comprises a piston 13 which includes an annular seal 14, in this embodiment an O-ring, and is a sealing fit in the respective cylinder 7, and a rod 15 which is connected to the piston 13, with the rod 15 being extended from the upper surface 4 of the fixture block 3 through the respective apertures 10 on introducing hydraulic fluid into the cavity 9 and retracted on withdrawing hydraulic fluid from the cavity 9. Preferably, the annular seal 14 is formed from an elastomeric material, such as buna rubber. In this embodiment each of the rods 15 is provided with an endcap 17. Preferably, the endcaps 17 are formed of a relatively soft material, such as a plastic, so as not to mar the surface of a supported workpiece. Preferably, the endcaps 17 are formed of a material having a high coefficient of friction so as to provide improved grip to a supported workpiece.

The tooling fixture further comprises an accumulator 21 and a supply line 23 connecting a lower region of the accumulator 21 to the port 11 in the fixture block 3. The accumulator 21 holds a sufficient volume of hydraulic fluid as to be able to drive the piston assemblies 12 to the fully extended positions, which extension requires complete filling of the cavity 9 and the cylinders 7 with hydraulic fluid.

The tooling fixture further comprises a pressure sensor 25 and a first valve 27 in the supply line 23, the pressure sensor 25 being provided to detect the hydrostatic pressure of the hydraulic fluid in the cavity 9 and the first valve 27 being provided to selectively connect the cavity 9 and the accumulator 21. In this embodiment the pressure sensor 25 is an electronic sensor which generates a voltage proportional to the detected pressure. In alternative embodiments the pressure sensor 25 could be a pneumatic or mechanical sensor which generates a pneumatic or mechanical signal indicative of the detected pressure. In this embodiment the first valve 27 is an electrically-operated, normally-closed valve. In an alternative embodiment the first valve 27 could be a pneumatic or mechanical valve which is operated in response to a pneumatic or mechanical signal.

The tooling fixture further comprises a second valve 29, in this embodiment a pilot-operated, spring-return two-position valve which includes first, second and third ports 31, 33, 35. The first port 31 of the second valve 29 is connected by a line 30 to an upper region of the accumulator 21. The third port 35 of the second valve 29 is connected by a line 37 to a vacuum source (not illustrated). In the first position of the second valve 29 the first port 31 is connected to the second port 33. In the second position of the second valve 29 the first port 31 is connected to the third port 35 such that the vacuum source is connected to the accumulator 21.

The tooling fixture further comprises a third valve 39, in this embodiment a pilot-operated, spring-return two-position valve which includes first, second and third ports 41, 43, 45. The first port 41 of the third valve 39 is connected by a line 47 to the second port 33 of the second valve 29. The second port 43 of the third valve 39 is connected by a line 49 to atmosphere. The third port 45 of the third valve 39 is connected by a line 51 to a compressed air source (not illustrated). In a first position of the third valve 39 the first port 41 is connected to the second port 43 such that the second port 33 of the second valve 29 is connected to atmosphere, which second valve 29 when in the first position is connected to the accumulator 21. In the second position of the third valve 39 the first port 41 is connected to the third port 45 such that the compressed air source is connected to the second

port 33 of the second valve 29, which second valve 29 when in the second position is connected to the accumulator 21.

The tooling fixture further comprises a controller 53 for controlling the operation of the first, second and third valves 27, 29, 39 in response to the pressure signal generated by the pressure sensor 25. Where the tooling fixture is provided as part of a machine, such as a screen printing machine or a placement machine, the controller 53 can be configured either to operate in conjunction with the controller of the machine or be provided as part of the controller of the machine. In this embodiment the controller 53 is a programmable logic controller which executes programmed instructions. In an alternative embodiment the controller 53 could be a programmable computer.

One mode of operation of the tooling fixture will now be described with reference to Figures 2 to 4.

With the piston assemblies 12 in the lowered position, the first valve 27 closed and the second and third valves 29, 39 in the first position, as illustrated in Figure 2, a workpiece 55 is fixed at a position spaced above the upper surface 4 of the fixture block 3. In this embodiment the workpiece 55 is a printed circuit board 57 having a lower surface populated with electronic components 59.

Under the control of the controller 53, the first valve 27 is opened and the second valve 39 switched to the second position, allowing compressed air to flow into the accumulator 21 and force fluid from the accumulator 21 into the cavity 9. This fluid flow causes the pistons 13 of the piston units 12 to be driven upwards in the respective cylinders 7, thereby causing the rods 15 of the piston units 12 to be extended from the upper surface 4 of the fixture block 3 and approach the populated printed circuit board 57.

As illustrated in Figure 3, this driving of the piston units 12 and extension of the rods 15 continues until ones of the rods 15 contact the lower surface of the populated printed circuit board 57. When one of the rods 15, the rightmost in Figure 4, contacts a component 59 on

the lower surface of the printed circuit board 57, that one rod 15 is not extended any further because the reaction of the component 59 on the rod 15 is such as to cause the fluid to flow preferentially into the cylinders 7 housing the other piston units 12 which are free to move and hence offer less resistance to the fluid flow. This filling of selective ones of the cylinders 7 continues as each rod 15 contacts a component 59 or the lower surface of the printed circuit board 57 until such point that each of the rods 15 contacts the workpiece 55, as illustrated in Figure 4. At that point, fluid flow is prevented and the pressure in the cavity 9 rises rapidly. When a predetermined pressure is detected by the pressure sensor 25, the first valve 27 is closed and the third valve 39 allowed to return to the first position under the control of the controller 53.

In this fully supported position, the upper surface of the printed circuit board 57 can be acted upon, as for example by a printing head of a screen printing machine or in the placement of further components 59 by a placement machine. With the volume of the fluid in the cylinders 7 and the cavity 9 fixed, the workpiece 55 will not flex in response to the application of a force along the row of rods 15 and a force applied locally to the workpiece 55 at a single point will be resisted by the stiffness provided by the viscous flow between the cylinders 7. Where the tooling fixture is used in a screen printing machine, the rows of rods 15 can be aligned with the screen printing head so that the force applied by the printing head along the line of the solder paste is resisted by the rows of rods 15.

When the processing of the workpiece 55 has been completed, under the control of the controller 53, the second valve 29 is switched to the second position and the first valve 27 opened such as to connect the vacuum source to the accumulator 21, whereby fluid is withdrawn from the cavity 9 into the accumulator 21. This withdrawal of fluid from the cavity 9 causes the piston units 12 to be lowered and the rods 15 to be retracted into the fixture block 3. After a predetermined period of time sufficient to allow all of the rods 15 to be fully retracted, the first valve 27 is closed and the second valve 29 allowed to return to the first position. The workpiece 55 can then be removed and the tooling fixture operated again to support another workpiece 55.

Another mode of operation of the tooling fixture will be described hereinbelow.

Under the control of the controller 53, with the platform in the lowered position, the first valve 27 is opened and the third valve 39 switched to the second position such as to allow compressed air to flow into the accumulator 21 and cause the piston units 12 to be driven to the extended position. In allowing compressed air to flow into the accumulator 21, fluid is forced from the accumulator 21 into the cavity 9. This fluid flow causes the pistons 13 of the piston units 12 to be driven upwards in the respective cylinders 7, thereby causing the rods 15 of the piston units 12 to be extended from the upper surface 4 of the fixture block 3. With the rods 15 in the fully extended position, and under the control of the controller 53, the third valve 39 is switched to the first position.

A workpiece 55 is then fixed at a position spaced above the upper surface 4 of the fixture block 3. In this embodiment the workpiece 55 is a printed circuit board 57 having a lower surface populated with electronic components 59.

Under the control of the controller 53, the platform is then raised so that, as each rod 15 contacts a component 59 or the lower surface of the workpiece, those rods 15 push down the pistons 13 into the cylinders 7, displacing fluid from the cavity 9 into the accumulator 21. Back pressure due to viscosity of the fluid maintains the rods 15 in the extended position until engaged by the workpiece 55. When the platform reaches its upper position the controller 53 closes the first valve 27, locking the rods 15 in position.

In this fully supported position, the upper surface of the printed circuit board 57 can be acted upon, as for example by a printing head of a screen printing machine or in the placement of further components 59 by a placement machine.

When the processing of the workpiece 55 has been completed, under the control of the controller 53, the platform is lowered. The workpiece 55 can then be removed and the tooling fixture operated again to support another workpiece 55.

As should be appreciated, the tooling fixture does not require any prior configuration when introducing a different workpiece 55. Rather, the tooling fixture conforms automatically to the lower surface of the workpiece 55 regardless of the position or height of any features on that surface.

In an alternative embodiment the accumulator 21 and the second and third valves 29, 39 could be replaced by a drive piston which is coupled to an actuator and slideably fitted within a master cylinder holding hydraulic fluid. In operation, the actuator raises the drive piston to draw fluid into the master cylinder from the cavity 9 and lowers the drive piston to force fluid from the master cylinder into the cavity 9.

Figure 5 schematically illustrates a tooling fixture in accordance with a second embodiment of the present invention.

The tooling fixture of this embodiment is quite similar to that of the above-described first embodiment, and thus, in order to avoid unnecessary duplication of description, only the differences will be described in detail, with like parts being designated by like reference signs.

This embodiment differs from that of the above-described first embodiment in that the fixture block 3 includes a plurality of ports 11 associated with respective ones of the rows of cylinders 7.

Operation is the same as for the above-described first embodiment.

Figure 6 schematically illustrates a tooling fixture in accordance with a third embodiment of the present invention.

The tooling fixture of this embodiment is quite similar to that of the above-described second embodiment, and thus, in order to avoid unnecessary duplication of description, only the

differences will be described in detail, with like parts being designated by like reference signs.

This embodiment differs from that of the above-described second embodiment in that each of the rows of cylinders 7 in the fixture block 3 is connected by a separate manifold cavity 9.

Operation is the same as for the above-described second embodiment.

Figure 7 schematically illustrates a tooling fixture in accordance with a fourth embodiment of the present invention.

The tooling fixture of this embodiment is quite similar to that of the above-described third embodiment, and thus, in order to avoid unnecessary duplication of description, only the differences will be described in detail, with like parts being designated by like reference signs.

This embodiment differs from that of the above-described third embodiment in that each of the separate manifold cavities 9 are connected to the supply line 23 through a separate valve 27.

Operation of this tooling fixture is the same as for the above-described third embodiment, with all of the valves 27 being simultaneously closed when the predetermined pressure is detected by the pressure sensor 25. This embodiment advantageously allows for ones of the rows of cylinders 7 to be isolated from the supply line 23, by maintaining the respective valves 27 closed, where the workpiece 55 does not span those rows of cylinders 7 and hence piston units 12, thereby minimising the necessary transfer of fluid to ensure fully supporting the workpiece 55.

The tooling fixture of this embodiment is particularly applicable where a relatively high force is applied to the workpiece 55 during processing and where a force is applied simultaneously across one row of the rods 15, such as applied by a screen printing head, as

the separation of each manifold cavity 9 by the valves 27 prevents fluid transfer to adjacent manifold cavities 9. The tooling fixtures of the second and third embodiments are more suited to applications where relatively a light force is applied to the workpiece 55 for a short period of time, such as exists in placement machines, as under those conditions the inherent stiffness prevents a single rod 15 or group of rods 15 from being depressed.

Figure 8 illustrates one tooling fixture module 61 of a tooling fixture in accordance with a fifth embodiment of the present invention.

In this embodiment the tooling fixture is constructed from a plurality of the tooling fixture modules 61, with the number of tooling fixture modules 61 incorporated being determined by the size of the workpiece to be supported. This tooling fixture module is adapted to be incorporated in the tooling fixture of the above-described third and fourth embodiments.

The tooling fixture module 61 comprises a main body 63, in this embodiment an elongate body, having upper and lower, in this embodiment substantially parallel, surfaces 64, 65, and including first and second rows of cylinders 67 which in this embodiment extend substantially orthogonally to the upper surface 64 thereof.

The tooling fixture module 61 further comprises a first, lower member 68 which is fixed to the lower surface 65 of the main body 63, and includes first and second cavities 69, in this embodiment elongate channels which act as manifolds, connecting ones, in this embodiment the lower, ends of the cylinders 67 in the respective rows of the cylinders 67, and first and second ports 71 in fluid communication with respective ones of the first and second cavities 69. In a preferred embodiment a gasket can be located between the lower member 68 and the main body 63 to ensure a fluid-tight seal.

The tooling fixture module 61 further comprises a second, upper member 73 which is fixed to the upper surface 64 of the main body 63 and includes first and second rows of apertures 75 corresponding to the rows of cylinders 67 in the main body 63.

The tooling fixture module 61 further comprises a plurality of piston units 77 slideably disposed in respective ones of the cylinders 67 such as to be driven on applying a hydraulic pressure in the respective ones of the cavities 69. In the same manner as the above-described embodiments, each piston assembly 77 comprises a piston 79 which includes an annular seal 81, in this embodiment an O-ring, and is a sealing fit in the respective cylinder 67, and a rod 83 which is connected to the piston 79, with the rods 83 being extendable through the upper member 73 on introducing hydraulic fluid into the cavities 69. For clarity of illustration, only two piston units 77 are illustrated.

Figures 9 to 12 illustrate a tooling fixture in accordance with a sixth embodiment of the present invention.

The tooling fixture comprises a fixture block 91 having upper and lower, in this embodiment substantially parallel, surfaces 92, 93, the upper surface 92 defining a surface over which a workpiece is to be supported and the lower surface 93 being supported on a platform which can be of fixed position or moved vertically to raise or lower the fixture block 91.

The fixture block 91 includes a plurality of cylinders 97, which in this embodiment extend substantially orthogonally to the upper surface 94 thereof and are arranged in first and second parallel rows, and first and second cavities 98, which act as manifolds and connect ones, in this embodiment the lower ends of the cylinders 97 of the respective ones of the first and second rows of cylinders 97. The fixture block 91 further includes first and second ports 99 in fluid communication with respective ones of the first and second manifold cavities 98, an elongate flow channel 100 extending through an upper region thereof and in fluid communication with each of the cylinders 97, and a third port 101 in communication with the flow channel 100. The third port 101 is connected by a first pneumatic supply line 102 to a first pneumatic supply (not illustrated).

The tooling fixture further comprises a plurality of piston assemblies 103 disposed in respective ones of the cylinders 97. In this embodiment each piston assembly 103 is retained in the respective cylinder 97 by a C-clip. As illustrated in Figures 11 and 12, each

piston assembly 103 comprises a piston sleeve 104, in this embodiment an elongate, cylindrical tubular element, having openings 105, 106 at the ends thereof, which is a tight fit in the respective cylinder 97, and a piston unit 107 which is slideably disposed within the piston sleeve 104.

The piston sleeve 104 includes first and second spaced annular cylinder seals 108, in this embodiment O-rings, at the upper, outer end thereof to maintain a sealing fit with the respective cylinder 97, and an annular groove 109, which is in fluid communication with the flow channel 100. The piston sleeve 104 further includes first and second apertures 111 in the peripheral wall thereof which provide a fluid communication path between the internal volume thereof and the annular groove 109. The piston sleeve 104 further includes an annular piston rod seal 112 in the inner surface thereof at the same axial position as the first cylinder seal 108 to maintain a sealing fit with the piston unit 107.

The piston unit 107 comprises a piston 115 which includes an annular piston seal 117, in this embodiment an O-ring, and is a sealing fit in the respective piston sleeve 104, and a rod 119 which is connected to the piston 115, with the rod 119 being a sealing fit in the piston rod seal 112 and extendable from the upper surface 92 of the fixture block 91 on introducing hydraulic fluid into the respective manifold cavity 98. With this construction, a chamber 121 is defined within the piston sleeve 104 between the piston rod seal 112 and the piston seal 117, with the apertures 111 serving as inlet or outlet ports.

The fixture block 91 further includes a piston cavity 122, in this embodiment an elongate cavity, and a drive piston 123 which includes annular seals 127, in this embodiment O-rings, and is a sealing fit in the piston cavity 122. The piston cavity 122 includes first and second ports 128, 129 at the opposed ends thereof. The drive piston 123 is slideably disposed in the piston cavity 122 and defines a fluid reservoir 131 containing hydraulic fluid, the volume of which reservoir 131 is sufficient as to be able to drive the piston units 107 to the fully extended positions, which extension requires complete filling of the manifold cavities 98 and the piston sleeves 104, and is controlled by movement of the drive piston 123. The first

port 128 of the piston cavity 122 is connected by a second pneumatic supply line 133 to a second pneumatic supply (not illustrated).

The tooling fixture further comprises a fluid supply line 135 connecting the ports 99 of the manifold cavities 98 and the second port 129 of the piston cavity 122, and a valve unit 136 which comprises first and second valves 137, 139, in this embodiment a pilot-operated, spring-return two position valve and a one-way valve respectively, connected in parallel to the fluid supply line 135, with the pilot of the first valve 137 being connected to the first pneumatic supply line 102 and the second valve 139 being configured to allow flow only from the fluid reservoir 131 into the manifold cavities 98. In the first position of the first valve 137, the first valve 137 is closed and flow is possible only via the one-way valve 139. In the second position of the first valve 137, the first valve 137 is open and fluid is able to flow therethrough.

The tooling fixture further comprises a controller (not illustrated) for controlling the operation of the first and second pneumatic supplies. Where the tooling fixture is provided as part of a machine, such as a screen printing machine or a placement machine, the controller can be configured either to operate in conjunction with the controller of the machine or be provided as part of the controller of the machine. In this embodiment the controller is a programmable controller which executes programmed instructions stored in a memory. In an alternative embodiment the controller could be a programmed computer.

Operation of the tooling fixture will now be described hereinbelow.

With the piston units 107 in the lowered position, a workpiece 145 is fixed at a position spaced above the upper surface 92 of the fixture block 91. In this embodiment the workpiece 145 is a printed circuit board 147 having a lower surface populated with electronic components 149.

With the first pneumatic supply de-actuated and the first valve 137 in the first position, the drive piston 123 is driven by applying a predetermined pneumatic pressure through the

second pneumatic supply line 133. This pneumatic pressure causes the drive piston 123 to be moved forwardly and the hydraulic fluid in the reservoir 131 to be forced via the second valve 139 through the fluid supply line 135 and into the manifold cavities 98 and the piston sleeves 104. This fluid flow causes the pistons 115 of the piston units 107 to be driven upwards in the respective piston sleeves 104, thereby causing the rods 119 of the piston units 107 to be extended from the upper surface 92 of the fixture block 91 and approach the populated printed circuit board 147.

This driving of the piston units 107 and extension of the rods 119 continues as ones of the rods 119 contact the lower surface of the populated printed circuit board 147. When ones of the rods 119 contact a component 149 on the lower surface of the printed circuit board 147, that one rod 119 is not extended any further because the reaction of the component 149 on the rod 119 is such as to cause the fluid to flow preferentially into the piston sleeves 104 housing the other piston units 107 which are free to move and hence offer less resistance to the fluid flow. This filling of selective ones of the piston sleeves 104 continues as each rod 119 contacts a component 149 or the lower surface of the printed circuit board 147 until such point that all of the rods 119 contact the workpiece 145, as illustrated in Figure 9. At that point, the pressure in the manifold cavities 98 rises rapidly. When the pressure in the manifold cavities 98 reaches the predetermined pressure of the first pneumatic supply, movement of the drive piston 123 ceases as the pressures on the opposed driving faces of the drive piston 123 are equal. At this point, the first pneumatic supply can be de-actuated, with fluid flow from the manifold cavities 98 being prevented by the second valve 139.

In this fully supported position, the upper surface of the printed circuit board 147 can be acted upon, as for example by a printing head of a screen printing machine or in the placement of further components by a placement machine. With the volume of the fluid in the piston sleeves 104 and the manifold cavities 98 fixed, the workpiece 145 will not flex in response to the application of a force along the row of rods 119 and a force applied locally to the workpiece 145 at a single point will be resisted by the stiffness provided by the viscous flow between the piston sleeves 104. Where the tooling fixture is used in a screen printing machine, the rows of rods 119 can be aligned with the screen printing head so that

the force applied by the printing head along the line of the solder paste is resisted by the rows of rods 119.

When the processing of the workpiece 145 has been completed, under the control of the controller, a pneumatic pressure is introduced into the first pneumatic supply line 102, which pressure switches the first valve 137 to the second position, thereby allowing fluid flow through the first valve 137 from the manifold cavities 98, and causes the piston units 107 to be driven downwards to the retracted position by the action of the pneumatic pressure acting in the chambers 121 in the piston assemblies 103. As the piston units 107 are driven to the retracted position, fluid is transferred from the manifold cavities 98 to the reservoir 131, which fluid transfer causes the drive piston 123 to be moved rearwardly to the original position. After a predetermined period of time sufficient to allow all the piston units 107 to be fully retracted, the pneumatic pressure in the first pneumatic supply line 102 is de-actuated, thereby allowing the first valve 137 to return to the first position. The workpiece 145 can then be removed and the tooling fixture operated again to support another workpiece 145.

Figure 13 schematically illustrates a tooling fixture in accordance with a seventh embodiment of the present invention.

The tooling fixture of this embodiment is quite similar to that of the above-described sixth embodiment, and thus, in order to avoid unnecessary duplication of description, only the differences will be described in detail, with like parts being designated by like reference signs. This embodiment differs from that of the above-described sixth embodiment in the manner in which the piston units 107 are returned to the retracted position.

This embodiment differs from the above-described sixth embodiment in that the fixture block 91 further includes a second piston cavity 152, in this embodiment an elongate cavity, and a second drive piston 153 which includes annular seals 157, in this embodiment O-rings, and is a sealing fit in the second piston cavity 152. The second piston cavity 152 includes first and second ports 158, 159 at the opposed ends thereof. The second drive piston 153 is

slideably disposed in the piston cavity 152 and defines a second fluid reservoir 161 containing hydraulic fluid, the volume of which reservoir 161 is sufficient as to be able to drive the piston units 107 to the fully retracted positions, which retraction requires complete filling of the return chambers 121 in the piston assemblies 103, and is controlled by movement of the second drive piston 153.

This embodiment further differs from the above-described sixth embodiment in that the first pneumatic supply line 102 is connected not to the pilot of the first valve 137 and the port 101 in communication with the flow channel 100, but rather the pilot of the first valve 137 and the first port 158 of the second piston cavity 152.

This embodiment further differs from the above-described sixth embodiment in including a second fluid supply line 163 connecting the second port 159 of the second piston cavity 152 to the port 101 of the flow channel 100.

Operation of this tooling fixture is essentially the same as that of the above-described sixth embodiment, but instead of the piston units 107 being returned by the delivery of the second pneumatic pressure directly into the return chambers 121 in the piston assemblies 103, the second pneumatic pressure acts on the second drive piston 153 to force fluid from the second fluid reservoir 161 into the return chambers 121 in the piston assemblies 103.

Figure 14 illustrates a tooling fixture in accordance with an eighth embodiment of the present invention.

The tooling fixture comprises a fixture block 191 having upper and lower, in this embodiment substantially parallel, surfaces 192, 193, the upper surface 192 defining a surface over which a workpiece is to be supported and the lower surface 193 being supported on a platform which can be of fixed position or moved vertically to raise or lower the fixture block 191.

The fixture block 191 includes a plurality of bores 197, which in this embodiment extend substantially orthogonally to the upper surface 192 thereof and are arranged as a plurality of parallel rows, and a cavity 198, which acts as a manifold and connects ones, in this embodiment the lower, ends of the bores 197. The fixture block 191 further includes a port 199 in fluid communication with the manifold cavity 198.

The tooling fixture further comprises a plurality of piston assemblies 202 disposed in respective ones of the bores 197. In this embodiment each piston assembly 202 is retained in the respective bore 197. Each piston assembly 202 comprises a piston sleeve 203, in this embodiment a cylindrical tubular element having openings 204, 205 at the ends thereof, which is an interference fit in the respective bore 197, and a piston unit 206 which is slideably disposed within the piston sleeve 203.

The piston sleeve 203 includes an annular rod seal 212, in this embodiment an O-ring, at the upper, inner end thereof to maintain a sealing fit with the piston unit 206.

The piston unit 206 comprises a rod 219 which is a sealing fit in the piston rod seal 212 and extendable from the upper surface 192 of the fixture block 191 on introducing fluid into the manifold cavity 198. The piston rod 219 includes a stop 220, in this embodiment a C-clip, at the lower end thereof to prevent the rod 219 from being driven out of the piston sleeve 203 on introducing fluid into the manifold cavity 198.

The fixture block 191 further includes a piston cavity 222, in this embodiment an elongate cavity, one end of which is closed and the other end of which is open, and a drive piston 223 which includes an annular seal 227, in this embodiment an O-ring, and is a sealing fit in the piston cavity 222. The piston cavity 222 includes a port 229 in the closed end thereof. The drive piston 223 is slideably disposed in the piston cavity 222 and defines a fluid reservoir 231 containing hydraulic fluid, the volume of which reservoir 231 is sufficient as to be able to drive the piston rods 219 to the fully extended positions, which extension requires complete filling of the manifold cavity 198, and is controlled by movement of the drive piston 223.

The tooling fixture further comprises a pneumatic actuator 232 which includes a drive rod 233 connected to the drive piston 223 for driving the drive piston 223 on actuation thereof. In this embodiment the pneumatic actuator 232 includes first and second ports 234, 235 connected respectively to first and second pneumatic supply lines 236, 237 to which pneumatic supplies (not illustrated) are connected to extend and retract the drive rod 233 respectively.

The tooling fixture further comprises a fluid supply line 238 connecting the port 199 of the manifold cavity 198 and the port 229 of the piston cavity 222, and a valve unit 239 which comprises first and second valves 240, 241, in this embodiment a pilot-operated, spring-return two position valve and a one-way valve respectively, connected in parallel in the fluid supply line 238, with the pilot of the first valve 240 being connected to the second pneumatic supply line 237 and the second valve 241 being configured to allow flow only from the reservoir 231 into the manifold cavity 198. In the first position of the first valve 240, the first valve 240 is closed and flow is possible only via the one-way valve 241. In the second position of the first valve 240, the first valve 240 is open and fluid is able to flow therethrough.

The tooling fixture further comprises a controller (not illustrated) for controlling the operation of the first and second pneumatic supplies. Where the tooling fixture is provided as part of a machine, such as a screen printing machine or a placement machine, the controller can be configured either to operate in conjunction with the controller of the machine or be provided as part of the controller of the machine. In this embodiment the controller is a programmable controller which executes programmed instructions stored in a memory. In an alternative embodiment the controller could be a programmed computer.

Operation of the tooling fixture will now be described hereinbelow.

With the piston units 206 in the lowered, retracted position, a workpiece 245 is fixed at a position spaced above the upper surface 192 of the fixture block 191. In this embodiment

the workpiece 245 is a printed circuit board 247 having a lower surface populated with electronic components 249.

With the second pneumatic supply de-actuated and the first valve 240 in the first position, the drive piston 223 is driven by applying a predetermined pneumatic pressure to the first pneumatic supply line 236. This pneumatic pressure actuates the pneumatic actuator 232 and causes the drive piston 223 to be moved forwardly and the fluid in the reservoir 231 to be forced via the second valve 241 through the fluid supply line 238 and into the manifold cavity 198. This fluid flow causes the piston units 206 to be driven upwards in the respective piston sleeves 203, thereby causing the rods 219 of the piston units 206 to be extended from the upper surface 192 of the fixture block 191 and approach the populated printed circuit board 247.

This driving of the piston units 206 and extension of the rods 219 continues as ones of the rods 219 contact the lower surface of the populated printed circuit board 247. When ones of the rods 219 contact a component 249 on the lower surface of the printed circuit board 247, that one rod 219 is not extended any further because the reaction of the component 249 on the rod 219 is such as to cause the other piston units 206 to move which offer less resistance to the fluid flow. This filling of the manifold cavity 198 continues as each rod 219 contacts a component 249 or the lower surface of the printed circuit board 247 until such point that all of the rods 219 contact the workpiece 245, as illustrated in Figure 14. At that point, the pressure in the manifold cavity 198 rises rapidly. When the pressure in the manifold cavity 198 reaches the predetermined pressure of the first pneumatic supply, movement of the drive piston 223 ceases as the pressures on the opposed driving faces of the drive piston 223 are equal. At this point, the first pneumatic supply can be de-actuated, with fluid flow from the manifold cavity 198 being prevented by the second valve 241.

In this fully supported position, the upper surface of the workpiece 245 can be acted upon, as for example by a printing head of a screen printing machine or in the placement of further components by a placement machine. With the volume of the fluid in the manifold cavity 198 fixed, the workpiece 245 will not flex in response to the application of a force along the

row of rods 219 and a force applied locally to the workpiece 245 at a single point will be resisted by the stiffness provided by the viscous flow in the manifold cavity 198. Where the tooling fixture is used in a screen printing machine, the rows of rods 219 can be aligned with the screen printing head so that the force applied by the printing head along the line of the solder paste is resisted by the rows of rods 219.

When the processing of the workpiece 245 has been completed, under the control of the controller, a pneumatic pressure is introduced into the second pneumatic supply line 237, which pressure switches the first valve 240 to the second position, thereby allowing fluid flow through the first valve 240 from the manifold cavity 198, and causes the drive piston 223 to be driven rearwardly by the pneumatic actuator 232 which causes fluid flow from the manifold cavity 198 into the reservoir 231 and in turn causes the piston units 206 to be driven downwards to the retracted positions. After a predetermined period of time sufficient to allow all of the piston units 206 to be fully retracted, the pneumatic pressure in the second pneumatic supply line 237 is de-actuated, thereby allowing the first valve 240 to return to the first position. The workpiece 245 can then be removed and the tooling fixture operated again to support another workpiece 245.

Figure 15 schematically illustrates a tooling fixture in accordance with a ninth embodiment of the present invention.

The tooling fixture of this embodiment is quite similar to that of the above-described eighth embodiment, and thus, in order to avoid unnecessary duplication of description, only the differences will be described in detail, with like parts being designated by like reference signs. This embodiment differs from that of the above-described eighth embodiment in the manner of the connection between the manifold cavity 198 and the fluid reservoir 231.

This embodiment differs from the above-described eighth embodiment in that the valve unit 239 is omitted and that the manifold cavity 231 is connected directly to the reservoir 231. In this embodiment the port 199 to the manifold cavity 198 is provided as an aperture between the manifold cavity 198 and the reservoir 231.

This embodiment further differs from the above-described eighth embodiment in that the pneumatic actuator 232 includes a clamp 251 for locking the position of the drive rod 233 and hence the drive piston 223 such as to fix the volume of fluid in the manifold cavity 198. In this embodiment the clamp 251 is a pneumatically-operated clamp which normally locks the drive rod 233 and is released on the application of a pneumatic pressure. The clamp 251 includes a port 253 connected to a third pneumatic supply line 255 to which is connected a third pneumatic supply (not illustrated).

Operation of this tooling fixture is essentially the same as that of the above-described eighth embodiment, but instead of fluid flow from the manifold cavity 198 being prevented by a check valve, the drive piston 223 is physically locked by the clamp 251, with the clamp 251 being released by actuating the third pneumatic supply when movement of the drive piston 223 is required.

Figures 16 to 21 illustrate one tooling fixture module 261 of a tooling fixture in accordance with a tenth embodiment of the present invention.

In this embodiment the tooling fixture is constructed from a plurality of the tooling fixture modules 261, with the number of tooling fixture modules 261 incorporated being determined by the size of the workpiece to be supported.

The tooling fixture module 261 comprises a main body 263, in this embodiment an elongate body, having upper and lower, in this embodiment substantially parallel, surfaces 264, 265. The main body 263 includes a plurality of cylinders 267, which in this embodiment extend substantially orthogonally to the upper surface 264 thereof and are arranged in first and second parallel rows, and first and second cavities 268, which act as manifolds and connect ones, in this embodiment the lower, ends of the cylinders 267 of the respective ones of the first and second rows of cylinders 267. The main body 263 further includes first and second ports in fluid communication with respective ones of the first and second manifold cavities 268.

The tooling fixture module 261 further comprises a connector block 270 and a valve unit 271 fixed to the lower surface 265 of the main body 263 at the opposed ends thereof, a fluid drive unit 272, in this embodiment formed as an elongate section extending between the connector block 270 and the valve unit 271, and first and second mounting blocks 273 fixed to the lower surface 265 of the main body 263 at positions between the connector block 270 and the valve unit 271.

The tooling fixture module 261 further comprises an upper member 273, in this embodiment a plate, which is fixed to the upper surface 264 of the main body 263 and includes first and second rows of apertures 275 corresponding to the rows of cylinders 267 in the main body 263.

The tooling fixture module 261 further comprises a plurality of piston assemblies 282 disposed in respective ones of the cylinders 267. In this embodiment each piston assembly 282 is retained in the respective cylinder 267. Each piston assembly 282 comprises a piston sleeve 283, in this embodiment a cylindrical tubular element, having openings 284, 285 at the ends thereof, which is an interference fit in the respective cylinder 267, and a piston unit 286 which is slideably disposed within the piston sleeve 283.

The piston sleeve 283 includes an annular rod seal 292, in this embodiment an O-ring, at the upper, inner end thereof to maintain a sealing fit with the piston unit 286, and an annular cylinder seal 295, in this embodiment an O-ring, at the lower, outer end thereof to maintain a sealing fit with the respective cylinder 267.

The piston unit 286 comprises a rod 299 which is a sealing fit in the piston rod seal 292 and extendable from the upper surface 264 of the main body 263 on introducing hydraulic fluid into the manifold cavities 268. The piston rod 299 includes a stop 301, in this embodiment a C-clip, at the lower end thereof to prevent the rod 299 from being driven out of the piston sleeve 283 on introducing fluid into the manifold cavities 268.

The fluid drive unit 272 includes a piston cavity 302, in this embodiment an elongate cavity, and a drive piston 303 which includes an annular seal 307, in this embodiment an O-ring, and is a sealing fit in the piston cavity 302. The piston cavity 302 is connected at one, rearward end to the connector block 270 and at the other, forward end to the valve unit 271. The drive piston 303 is slideably disposed in the piston cavity 302 and defines a fluid reservoir 305 containing hydraulic fluid, the volume of which reservoir 305 is sufficient as to be able to drive the piston units 282 to the fully extended positions, which extension requires complete filling of the manifold cavities 268 and the cylinders 267, and is controlled by movement of the drive piston 303.

As illustrated in Figures 20 and 21, the valve unit 271 comprises a main body 309, in this embodiment an elongate body, having a first port 311 at one end thereof in sealed connection with the fluid reservoir 305 and a second port 313 in the peripheral wall thereof in sealed connection with the manifold cavities 268, a piston unit 315 slideably disposed in the main body 309 between a first, open position (as illustrated in Figure 20) in which a fluid communication path is provided between the first and second ports 311, 313 and a second, closed position (as illustrated in Figure 21) in which no fluid communication path is provided between the first and second ports 311, 313, and a diaphragm seal 316 sealingly connecting the main body 309 and the piston unit 315 to prevent fluid flow therebeyond. The valve unit 271 further comprises a biasing element 317, in this embodiment a compression spring, which biases the piston unit 315 to the open position, and a screw adjuster 318 to allow adjustment of the biasing force of the biasing element 317. Pre-tensioning the biasing element 317 advantageously provides that, when the force required to start compressing the biasing element 317 has been exceeded, very little extra force is required to compress the biasing element 317.

The piston unit 315 comprises a piston 319 which includes a hollow bore 320 extending axially therethrough, one end of which is sealed by a rigid ball 322 press-fitted into the bore 320 and the other end of which is closed by a screw 323 attaching the flexible diaphragm 316. The piston 319 includes first, second and third groups of cross-drilled holes 324, 326 and 328 which provide a fluid flow path through the hollow bore 320 of the piston 319 to

the manifold cavities 268. The piston unit 315 further includes an annular piston seal 329, in this embodiment an O-ring, at the outer surface of the one end of the piston 319 to provide a tight seal between the piston unit 315 and the main body 309 when the piston unit 315 is in the closed position. In this embodiment the piston seal 329 engages an inwardly tapering surface of the main body 309 such as to provide a particularly tight seal and ensure closure of the manifold cavities 268 for as long as the pneumatic supply is maintained to the drive piston 319.

The tooling fixture further comprises a controller (not illustrated) for controlling the operation of the pneumatic supply and vacuum source. Where the tooling fixture is provided as part of a machine, such as a screen printing machine or a placement machine, the controller can be configured either to operate in conjunction with the controller of the machine or be provided as part of the controller of the machine. In this embodiment the controller is a programmable controller which executes programmed instructions stored in a memory. In an alternative embodiment the controller could be a programmed computer.

Operation of the tooling fixture is described hereinbelow.

With the piston units 286 in the lowered position, a workpiece (not illustrated) is fixed at a position spaced above the tooling fixture. Typically, the workpiece can be a printed circuit board having a lower surface populated with electronic components.

The pneumatic supply is then actuated to drive the drive piston 303 forwardly, which movement of the drive piston 303 causes fluid in the reservoir 305 to flow through the first group of apertures 324 in the piston 319, into the hollow body 320 of the piston 319, through the second group of apertures 326 in the piston 319 and into the manifold cavities 268. This fluid flow causes the piston units 286 to be driven upwards in the respective piston sleeves 283, thereby causing the rods 299 of the piston units 286 to be extended and approach the workpiece.

This driving of the piston units 286 and extension of the rods 299 continues as ones of the rods 299 contact the lower surface of the workpiece. When ones of the rods 299 contact the lower surface of the workpiece, that one rod 299 is not extended any further because the reaction of the workpiece on the rod 299 is such as to cause the other piston units 286 to be moved which offer less resistance to the fluid flow. This filling of the manifold cavities 268 continues as each rod 299 contacts the lower surface of the workpiece until such point that all of the rods 299 contact the workpiece. At that point, the pressure in the manifold cavities 268 and the reservoir 305 rises rapidly. When the pressure reaches a predetermined pressure which is sufficient to overcome the biasing force of the biasing element 317, with the fluid acting on the one end of the piston 319 and through the third group of apertures 328 on the flexible diaphragm 316, the piston unit 315 is moved to the closed position, thereby closing the fluid communication path between the reservoir 305 and the manifold cavities 268 and fixing the volume of fluid in the manifold cavities 268. that the fluid pressure applied to the rods 150 to raise them is limited by the force applied by spring 240, which can be set by selecting a suitable spring and by adjustment of screw 250.

In this fully supported position, the upper surface of the workpiece can be acted upon, as for example by a printing head of a screen printing machine or in the placement of further components by a placement machine. With the volume of the fluid in the manifold cavities 268 fixed, the workpiece will not flex in response to the application of a force along each row of rods 299 and a force applied locally to the workpiece at a single point will be resisted by the stiffness provided by the viscous flow in the manifold cavities 268. Where the tooling fixture is used in a screen printing machine, the rows of rods 299 can be aligned with the screen printing head so that the force applied by the printing head along the line of the solder paste is resisted by the rows of rods 299.

When the processing of the workpiece has been completed, under the control of the controller, the pneumatic supply is de-actuated, causing the biasing element 317 to return the piston unit 315 to the open position. A vacuum source (not illustrated) is then applied to the piston cavity 302 to draw the drive piston 303 rearwardly to the original position, which movement of the drive piston 303 causes fluid flow from the manifold cavities 268 into the

reservoir 305 and in turn causes the piston units 286 to be driven downwards to the retracted position. After a predetermined period of time sufficient to allow all the piston units 286 to be fully retracted, the vacuum source can be de-actuated. The workpiece can then be removed and the tooling fixture operated again to support another workpiece.

Figures 22 to 25 illustrate a tooling fixture module of a tooling fixture in accordance with an eleventh embodiment of the present invention.

The tooling fixture of this embodiment is quite similar to that of the above-described tenth embodiment, and thus, in order to avoid unnecessary duplication of description, only the differences will be described in detail, with like parts being designated by like reference signs. This embodiment differs from that of the above-described tenth embodiment principally in the construction of the fluid drive unit 272.

This embodiment differs from the above-described tenth embodiment in that the fluid drive unit 272 does not include a drive piston 303, but rather an inflatable bladder 331, the internal volume of which defines the fluid reservoir 305. In this embodiment the bladder 331 is an elongate bladder located about a hollow shaft 333 in an elongate cavity 335 in the main body 263. The hollow shaft 333 includes a plurality of apertures 337 along the length thereof and defines the principal flow path from the reservoir 305 to the valve unit 271. As illustrated in Figure 25, the cavity 335 includes a plurality of flutes 339 in the surface thereof which act to channel pressure or vacuum applied to the bladder 331.

This embodiment also differs in that the valve unit 271 includes a flow control element 341 to control the flow of fluid from the reservoir 305 through the valve unit 271, but provide substantially unimpeded flow in the opposite direction. In this embodiment the flow control element 341 comprises an annulus of resilient material mounted such that flow from the reservoir 305 is through only the central aperture and flow into the reservoir 305 is through the central aperture and around the periphery thereof, the periphery being deflected by fluid flow into the reservoir 305.

Operation of this tooling fixture is essentially the same as that of the above-described tenth embodiment, but instead of fluid flow being driven by a drive piston, the fluid flow is driven by collapsing or inflating the bladder 331.

Finally, it will be understood that the present invention has been described in its preferred embodiments and can be modified in many different ways without departing from the scope of the invention as defined by the appended claims.

CLAIMS

1. A tooling fixture comprising:
a fixture block containing a plurality of parallel cylinders formed therein;
a plurality of piston assemblies slideably fitted into said plurality of cylinders such that a portion of said piston assemblies can extend from the surface of said fixture block when said piston assemblies slide within said cylinders;
at least one fluid reservoir connected in flow communication with said cylinders below said pistons; and
means for reversibly forcing fluid from said reservoir into said cylinders.
2. The tooling fixture of claim 1, wherein said fluid control means comprises a pneumatic pressure source in fluid communication with the at least one reservoir.
3. The tooling fixture of claim 1, wherein the fluid control means comprises a main piston slideably disposed in the reservoir, and a drive unit for sliding the main piston in the reservoir.
4. The tooling fixture of claim 3, wherein said means for sliding said main piston within said reservoir comprises a source of pressurized fluid connected to said reservoir interior at a location, with respect to said main piston, opposite the connection between said reservoir and said cylinders.
5. The tooling fixture of claim 3, wherein the drive unit comprises a hydraulic cylinder connected to said main piston via a rod.
6. The tooling fixture of claim 3, wherein the drive unit comprises a pneumatic cylinder connected to said main piston via a rod.
7. The tooling fixture of claim 1, further comprising means connected between said fluid reservoir and said cylinders for controlling the flow of fluid therebetween.

8. The tooling fixture of claim 7, wherein said means for controlling the flow of fluid comprises a pressure-sensitive shut-off valve that automatically stops the flow of fluid into the cylinders when the pressure exerted by the fluid reaches a predetermined value.
9. A tooling fixture, comprising:
 - a base; and
 - at least one support module mounted on said base, said support module comprising:
 - a module body containing a plurality of (parallel) cylinders formed therein aligned in at least one row, and at least one manifold connecting said aligned row of cylinders;
 - at least one fluid reservoir connected in flow communication with said manifold;
 - a plurality of piston assemblies slideably fitted into said plurality of cylinders such that a portion of said piston assemblies can extend from the surface of said module body when said piston assemblies slide within said cylinders; and
 - means for reversibly forcing fluid from said reservoir into said manifold and from said manifold into said cylinders.
10. The tooling fixture of claim 9, wherein said means for forcing fluid from said reservoir comprises a main piston slideably fitted within said reservoir, and means for sliding said main piston within said reservoir.
11. The tooling fixture of claim 10, wherein said means for sliding said main piston within said reservoir comprises a source of pressurized fluid connected to said reservoir interior at a location, with respect to said main piston, opposite the connection between said reservoir and said manifold.
12. The tooling fixture of claim 10, wherein said means for sliding said main piston within said reservoir comprises a hydraulic cylinder connected to said main piston via a rod.

13. The tooling fixture of claim 10, wherein said means for sliding said main piston within said reservoir comprises a pneumatic cylinder connected to said main piston via a rod.
14. The tooling fixture of claim 11, wherein said means for sliding said main piston further comprises a source of negative pressure connected to said reservoir interior at a location, with respect the main piston, opposite the connection between said reservoir and said manifold.
15. The tooling fixture of claim 9, further comprising:
 - a second manifold in said module body connecting the cylinders in each row, said second manifold being located on an opposite side of said piston assemblies from said first manifold; and
 - a second source of pressurized fluid connected to said second manifold.
16. The tooling fixture of claim 15, wherein said second source of pressurized fluid comprises:
 - a second fluid reservoir;
 - a second main piston slideably fitted within said second fluid reservoir; and
 - a source of pressurized fluid connected to said second fluid reservoir interior at a location, with respect to said second main piston, opposite the connection between said second reservoir and said second manifold.
17. The tooling fixture of claim 15, wherein said second source of pressurized fluid comprises a pneumatic pressure source.
18. The tooling fixture of claim 10, further comprising means connected between said fluid reservoir and said at least one manifold for controlling the flow of fluid therebetween.
19. The tooling fixture of claim 18, wherein said means for controlling the flow of fluid comprises a one-way check valve and a pneumatic valve in parallel combination.

20. The tooling fixture of claim 10, wherein said fluid reservoir comprises a cavity integrally formed in said module body.
21. The tooling fixture of claim 9, further comprising cylinder sleeve assemblies disposed in said cylinders between said piston assemblies and said cylinder walls.
22. The tooling fixture of claim 9, wherein said piston assemblies comprise a piston, and a rod of lesser diameter than said piston secured to a surface of said piston.
23. The tooling fixture of claim 10, wherein said fluid reservoir comprises a tube integrally attached to said module body.
24. The tooling fixture of claim 18, wherein said means of controlling the flow of fluid comprises a pressure-sensitive shut-off valve that automatically stops the flow of fluid into the cylinders when the pressure exerted by the fluid reaches a predetermined value.
25. The tooling fixture of claim 24, wherein said pressure sensitive shut-off valve comprises:
 - a second sliceable piston assembly disposed in said fluid reservoir between said first main piston and said manifold;
 - a second main piston having an axial bore formed therein, and at least two sets of radially oriented bores through said second main piston and intersecting with said second bore, and a rigid ball at a first end for sealing off said axial bore;
 - a spring connected at one end to said second main piston and at its other end to a screw for adjusting the force applied by said spring to said second piston; and
 - a diaphragm positioned between said main piston and said spring.
26. A tooling fixture for supporting a workpiece, comprising:
 - a base; and

at least one support module mounted on said base, said support module comprising:
a module body containing a plurality of cylinders formed therein aligned in at least one row, and interconnected at their lower ends by at least one manifold;
a hydraulic pressure tube integrally connected to said module body and in flow communication with said manifold and containing a main piston therein;
a control valve assembly connected between said hydraulic pressure tube and said manifold for controlling the flow of fluid therebetween;
a plurality of pistons slideably fitted into said plurality of cylinders such that a portion of said pistons can extend from a surface of said module towards said workpiece when said pistons slide within said cylinders; and
a pneumatic pressure source connected to said hydraulic fluid tube for applying a positive pneumatic pressure to said main piston.

27. The tooling fixture of claim 26, wherein said control valve assembly comprises a pressure-sensitive shut-off valve that prevents the flow of fluid from said hydraulic fluid tube into said manifold when the fluid pressure exceeds a predetermined value, and allows fluid to flow from said hydraulic fluid tube into said manifold when said fluid pressure is below a predetermined value.
28. The tooling fixture of claim 27, wherein said pressure sensitive shut-off valve comprises:
a second slideable piston assembly disposed in said fluid reservoir between said first main piston and said manifold;
a second main piston having an axial bore formed therein, and at least two sets of radially oriented bores through said second main piston and intersecting with said second bore, and a rigid ball at a first end for sealing off said axial bore;
a spring connected at one end to said second main piston and at its other end to a screw for adjusting the force applied by said spring to said second piston; and
a diaphragm positioned between said main piston and said spring.

29. The tooling fixture of claim 28, wherein said spring applies an amount of pressure on said piston equal and opposite to said predetermined value, such that when said fluid pressure exceeds said predetermined value, said piston slides toward said spring thereby forcing the valve assembly into a closed state preventing the further flow of fluid into the manifold.
30. A tooling fixture for supporting a workpiece, comprising:
a module body containing a plurality of cylinders formed therein, the lower portion of said plurality of cylinders being connected by a first manifold and the upper portion of said plurality of cylinders being connected by a second manifold;
a fluid reservoir integrally formed in said module body and containing a floating main piston therein;
a valve assembly comprising a one-way check valve and a pneumatic control valve in parallel combination and connected between said fluid reservoir and said first manifold for controlling the flow of fluid therebetween;
a plurality of pistons integrally connected to rods and slideably fitted into said plurality of cylinders such that said rods can extend from a surface of said module towards said workpiece upon sliding of said piston within said cylinders;
a first pneumatic pressure source connected to said fluid reservoir for providing pressure to said main piston; and
a second pneumatic pressure source connected to said second valve and said second manifold.
31. The tooling fixture of claim 30, wherein said second pneumatic pressure source applies pressure to said second valve and to said second manifold simultaneously opening said valve to allow fluid to flow from said first manifold into said fluid reservoir and forcing said rods to retract into said module body.
32. A tooling fixture for supporting a workpiece, comprising:

a module body containing a plurality of cylinders formed therein, the lower portion of said plurality of cylinders being connected by a first manifold and the upper portion of said plurality of cylinders being connected by a second manifold;

a first fluid reservoir integrally formed in said module body and containing a first floating main piston therein;

a second fluid reservoir integrally formed in said module body and containing a second main piston therein, said second fluid reservoir connected to said second manifold by a continuous flow path;

a valve assembly comprising a one-way check valve and a pneumatic control valve in parallel combination connected between said first fluid reservoir and said first manifold for controlling the flow of fluid therebetween;

a plurality of pistons integrally connected to rods and slideably fitted into said plurality of cylinders such that said rods can extend from a surface of said module towards said workpiece upon sliding of said pistons within said cylinders;

a first pneumatic pressure source connected to said first fluid reservoir for providing pressure to said first main piston; and

a second pneumatic pressure source connected to said second valve and said second fluid reservoir.

33. The tooling fixture of claim 32, wherein said second pneumatic pressure source simultaneously applies pressure to said second valve to cause it to open and allow fluid to flow from said first manifold into said first reservoir and to said second fluid reservoir such that fluid from said second fluid reservoir is forced through said continuous flow path into said second manifold to force said rods to retract into said module body.
34. A tooling fixture for supporting a workpiece, comprising:
a module body having a flat top surface with a plurality of apertures, and a first fluid reservoir cavity formed therein;
a plurality of rods slideably mounted in the apertures of said top surface and extending into said first fluid reservoir cavity;

a second fluid reservoir integrally formed with said module body and connected in flow communication with said first reservoir;
a main piston slideably fitted in said second fluid reservoir;
means for controlling the flow of fluid from said second reservoir to said first reservoir; and
means for sliding said main piston within said second reservoir.

35. The tooling fixture of claim 34, wherein said means for controlling the flow of fluid comprises a control valve assembly connected between said first and second reservoirs and in flow communication therewith.
36. The tooling fixture of claim 35, wherein said control valve assembly comprises a one-way check valve and a pneumatic control valve in parallel combination.
37. The tooling fixture of claim 36, wherein said means for sliding said main piston comprises a source of pressurized fluid connected to said second fluid reservoir interior at a location, with respect to said main piston, opposite said connection between said first and second fluid reservoirs.
38. The tooling fixture of claim 37, wherein said source of pressurized fluid comprises a pneumatic pressure source.
39. The tooling fixture of claim 36, wherein said means for sliding said main piston comprises a pneumatic cylinder connected at one end to said main piston via a connecting rod and to a first source of pneumatic pressure, and connected at its opposite end to a second source of pneumatic pressure.
40. The tooling fixture of claim 39, wherein said pneumatic control valve is connected to said first source of pneumatic pressure.

41. The tooling fixture of claim 40, wherein the application of pneumatic pressure opens said pneumatic control valve to allow fluid to flow from the first reservoir to the second reservoir while simultaneously causing the pneumatic cylinder to retract the main piston in the second reservoir.
42. The tooling fixture of claim 34, wherein said first and second reservoirs are separated by a wall, and said means for controlling the flow of fluid comprises an aperture of fixed size in said wall.
43. The tooling fixture of claim 42, wherein said means for sliding said main piston comprises a pneumatic cylinder connected at one end to said main piston via a connecting rod and to a first source of pneumatic pressure, and connected at its opposite end to a second source of pneumatic pressure.
44. The tooling fixture of claim 43, wherein said pneumatic cylinder further includes a clamp connected at one end for prohibiting said connecting rod from moving when in a closed state and allowing said connecting rod to move freely when in an open state.
45. The tooling fixture of claim 44, wherein said clamp is in said open state when pressure is applied thereto for permitting said connecting rod to extend and retract within said pneumatic cylinder and said second fluid reservoir, and in said closed state when pressure is removed from it prohibiting said connecting rod from extending and retracting within said pneumatic cylinder and said second fluid reservoir.
46. A method of supporting a workpiece, comprising the steps of:
providing a tooling fixture proximate the workpiece, the tooling fixture comprising:
a support module body having a plurality of moveable pistons fitted in a plurality of cylinders formed therein, said pistons being capable of extending through the top of said module body to contact said workpiece; and

applying pneumatic pressure to a piston contained in a fluid reservoir connected to said cylinders to move said piston and force fluid from said reservoir into said cylinders to force said pistons to emerge from said cylinders until they contact said workpiece.

47. The method of claim 46, further comprising the step of controlling a valve assembly positioned between said fluid reservoir and said cylinders to be in an open state prior to applying said pneumatic pressure to said reservoir piston.
48. The method of claim 47, further comprising the step of causing said valve to close when all of said pistons are in contact with and supporting the workpiece.
49. The method of claim 48, further comprising the step of opening and closing the valve assembly when the fluid pressure reaches a predetermined value.
50. The method of claim 49, further comprising the step of setting the predetermined value to be the same value required to place all of the pistons in contact with the workpiece.
51. A tooling fixture, comprising:
 - a source of fluid;
 - a fixture block;
 - a plurality of cylinders within the fixture block;
 - a valve connected with the source of fluid and with the cylinders for controlling the flow of a fluid therebetween;
 - a pressure sensor connected with the cylinders, the pressure sensor generating a signal that indicates a pressure of the fluid in the cylinders;
 - a plurality of pistons slideably fitted into respective ones of the plurality of cylinders, ends of the pistons extending from a surface of the fixture block; and
 - a controller connected with the pressure sensor and the valve.

52. The tooling fixture of claim 51, wherein the source of fluid comprises an accumulator including a fixed volume container connected at a bottom end with the valve and connected at a top end to a source of gas for applying a pneumatic pressure to the fluid.
53. The tooling fixture of claim 52, wherein the accumulator further comprises a source of vacuum connected with the fixed volume container for applying a negative pneumatic pressure to the fluid.
54. The tooling fixture of claim 53, further comprising a compressed air supply valve connecting the source of pneumatic pressure with the fixed volume container and a vacuum supply valve connecting the source of vacuum with the fixed volume container, the compressed air and vacuum supply valves being controlled in response to signals from the controller.
55. The tooling fixture of claim 54, wherein the vacuum supply valve includes a three-port valve for connecting the fixed volume container with the vacuum source and connecting the fixed volume container with the compressed air supply valve and the compressed air supply valve includes a three-port valve for connecting the vacuum supply valve with the compressed air supply and connecting the vacuum supply valve with an atmospheric vent.
56. The tooling fixture of claim 51, wherein the cylinders are arranged in a two-dimensional array.
57. The tooling fixture of claim 51, wherein the cylinders are arranged in a row.
58. The tooling fixture of claim 51, wherein the fixture block further comprises a plurality of block segments, and wherein at least one row of the cylinders is provided on each segment.

59. The tooling fixture of claim 51, wherein the controller closes the valve when the pressure of the fluid in the cylinders reaches a predetermined threshold.
60. The tooling fixture of claim 51, wherein the controller is a programmable controller executing programmed instructions stored in a memory.
61. The tooling fixture of claim 51, further comprising a printed circuit board disposed proximate to the surface of the fixture block within a screen printing machine.
62. The tooling fixture of claim 51, further comprising a printed circuit board disposed proximate to the surface of the fixture block within a placement machine.
63. The tooling fixture of claim 51, further comprising endcaps affixed to the ends of the pistons.
64. The tooling fixture of claim 51, wherein the pistons further comprise sealing rings, the sealing rings forming a sliding seal along walls of the cylinders.
65. A tooling fixture, comprising:
 - accumulator means for providing a hydraulic fluid;
 - valve means for opening and closing a fluid path from the accumulator means;
 - a plurality of cylinders connected with the valve means;
 - pressure sensing means for sensing a pressure of fluid in the cylinders;
 - control means for controlling the accumulator means and the valve means; and
 - a plurality of pistons slideably disposed in the plurality of cylinders, ends thereof extending from the cylinders.
66. A tooling fixture for supporting a printed circuit board, the fixture comprising:
 - a source of fluid;
 - a plurality of valves, each connected with the accumulator;
 - a plurality of block segments connected with respective ones of the valves;

a plurality of cylinders, the cylinders being arranged in a row within the block segments and the row of cylinders in each block segment being connected with the respective valve;
a plurality of pistons, the pistons being disposed in the cylinders, ends of the pistons extending from surfaces of the block segments;
a pressure sensor connected with the plurality of cylinders; and
a controller connected with the actuator, the plurality of valves, and the pressure sensor.

67. The tooling fixture of claim 66, wherein the source of fluid further comprises:
a fixed volume container connected at a bottom end thereof with the plurality of valves;
a source of compressed air;
a compressed air supply valve connecting the source of compressed air with a top end of the container;
a source of vacuum; and
a vacuum supply valve connecting the source of vacuum with the top end of the container;
wherein the controller is connected with the compressed air supply valve and the vacuum supply valve.
68. The tooling fixture of claim 66, wherein the controller controls the valves in response to signals from the pressure sensor.
69. The tooling fixture of claim 66, wherein a selected one of the plurality of valves is held closed so that cylinders connected with the selected valve are disabled.
70. A fixture block, comprising:
a manifold section, the manifold section including a groove along a top surface thereof and an outlet hole on an end thereof intersecting the groove;

a cylinder section mounted to the top surface of the manifold section, the cylinder section including a plurality of cylinder holes therethrough, the cylinder holes being aligned with the groove;

a top section mounted to a top surface of the cylinder section; and

a plurality of pistons slideably disposed in the cylinder holes, ends thereof extending through holes in the top section.

71. The fixture block of claim 70, further comprising a gasket disposed between the manifold section and the cylinder section.
72. A method of supporting a workpiece, comprising the steps of:
 - providing a fixture block proximate to the workpiece, the fixture block including a plurality of pistons disposed in a respective plurality of cylinders, ends of the pistons extending through a surface of the fixture block;
 - opening a valve connecting the plurality of cylinders with a source of hydraulic fluid;
 - applying a first force to the source of fluid to move the fluid out of the cylinders to pull the pistons toward the bottoms of the cylinders;
 - moving the fixture block to a predetermined distance from the workpiece;
 - applying a second force to the source of fluid to move the fluid into the cylinders to drive the pistons toward the tops of the cylinders, wherein ends of the pistons are extended from the surface of the block and contact a surface of the workpiece;
 - sensing a pressure of the fluid within the cylinders; and when the pressure reaches a predetermined threshold; and
 - closing the valve.
73. The method of claim 72, wherein the source of fluid comprises a fixed volume container connected at a bottom end with the valve and connected at a top end with a source of pneumatic pressure and a source of vacuum and wherein the step of applying the first force further comprises providing vacuum to the fixed volume container from the vacuum source and wherein the step of applying the second force further comprises providing pneumatic pressure to the container from the source of pneumatic pressure.

74. The method of claim 72, wherein the plurality of cylinders are arranged in a plurality of rows, cylinders in each row being interconnected and each row being connected with a respective plurality of segment valves, the segment valves connecting the rows of cylinders with the source of fluid, and wherein the step of closing the valve further comprises closing the plurality of segment valves.
75. The method of claim 74, further comprising selecting a row that is to remain unextended and closing the segment valve connected with the selected row prior to the step of applying the second force.
76. The method of claim 75, wherein the step of selecting further comprises determining a dimension of the workpiece and selecting the row to remain unextended based on the dimension of the workpiece.
77. The method of claim 72, wherein the workpiece is a printed circuit board within a screen printing machine.
78. The method of claim 72, wherein the workpiece is a printed circuit board within a placement machine.
79. A method of supporting a workpiece, comprising the steps of:
providing a fixture block proximate to the workpiece, the fixture block including a plurality of pistons disposed in a respective plurality of cylinders, ends of the pistons extending through a surface of the fixture block;
opening a valve connecting the plurality of cylinders with a source of hydraulic fluid;
applying a force to the source of fluid to move the fluid into the cylinders to drive the pistons to the tops of the cylinders, wherein the ends of the pistons are extended from the surface of the fixture block;

moving the fixture block toward the workpiece so that the ends of the pistons contact a surface of the workpiece; when the fixture block reaches a predetermine distance from the workpiece;
stopping the movement of the fixture block; and
closing the valve.

80. A tooling fixture for supporting a workpiece, comprising:
a body including a surface over which a workpiece is in use supported and a plurality of bores therein;
a plurality of supporting elements for supporting the workpiece, each slideably disposed in a respective one of the bores such as to be extendable from the surface of the body;
at least one fluid reservoir operably in fluid communication with the supporting elements such as to cause sliding of ones of the supporting elements on displacement of the fluid in the at least one fluid reservoir; and
fluid control means for displacing the fluid in the at least one reservoir such as to cause the supporting elements to be extended to a supporting position in contact with the workpiece and locking the supporting elements in the supporting position.

1 / 18




FIG. 1

THIS PAGE BLANK (USPTO)




FIG. 2

THIS PAGE BLANK (USPTO)

3 / 18




FIG. 3

THIS PAGE BLANK (USPTO)




FIG. 4

THIS PAGE BLANK (USPTO)

5 / 18




FIG. 5

THIS PAGE BLANK (USPTO)

6 / 18




FIG. 6

THIS PAGE BLANK (USPTO)

7 / 18




FIG. 7

THIS PAGE BLANK (USPTO)




FIG. 8

THIS PAGE BLANK (USPTO)

THIS PAGE BLANK (USPTO)

10 / 18




FIG. 10




FIG. 11




FIG. 12

THIS PAGE BLANK (USPTO)




FIG. 13

THIS PAGE BLANK (USPTO)




FIG. 14

THIS PAGE BLANK (USPTO)




FIG. 15

THIS PAGE BLANK (USPTO)

14 / 18





FIG. 19

THIS PAGE BLANK (USPTO)

15 / 18




FIG. 17




FIG. 18

THIS PAGE BLANK (USPTO)

16 / 18




FIG. 20




FIG. 21

THIS PAGE BLANK (USPTO)

17 / 18




FIG. 22




FIG. 23




FIG. 24

THIS PAGE BLANK (USPTO)

18 / 18




FIG. 25

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

Int. National Application No.

PCT/GB 00/02403

A. CLASSIFICATION OF SUBJECT MATTER

IPC 7 H05K13/00

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 H05K B41F

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

EPO-Internal, PAJ

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
A	GB 2 322 089 A (DEK PRINTING) 17 September 1997 (1997-09-17) the whole document	1,8,26, 30,32, 34,46, 51,65, 66,70,72
P,A	WO 00 08905 A (SMC PNEUMATICS) 17 February 2000 (2000-02-17) the whole document	1,8,26, 30,32, 34,46, 51,65, 66,70,72

☒ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents :

A document defining the general state of the art which is not considered to be of particular relevance

E earlier document but published on or after the international filing date

L document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)

O document referring to an oral disclosure, use, exhibition or other means

P document published prior to the international filing date but later than the priority date claimed

T later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

X document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

Y document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

A document member of the same patent family

Date of the actual completion of the international search

10 October 2000

Date of mailing of the international search report

18/10/2000

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax: (+31-70) 340-3016

Authorized officer

Loncke, J

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

International Application No
PCT/GB 00/02403

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
P,A	<p>EP 0 954 211 A (IMI NORGRN) 3 November 1999 (1999-11-03)</p> <p>the whole document _____</p>	<p>1,8,26, 30,32, 34,46, 51,65, 66,70,72</p>

THIS PAGE BLANK (USPTO)

INTERNATIONAL SEARCH REPORT

Information on patent family members

International Application No

PCT/GB 00/02403

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
GB 2322089 A	19-08-1998	EP 0960001 A	01-12-1999
		WO 9835780 A	20-08-1998
WO 0008905 A	17-02-2000	NONE	
EP 954211 A	03-11-1999	NONE	

THIS PAGE BLANK (USPTO)